WORK ORDER

Client:	
ShubhShree Engineering and Constructions Pvt Ltd	
Address:	
C/O Endress+Hauser Flowtec India Pvt Ltd , M-171-176 , Waluj MIDC , Aurangabad-4310136	

PO Number:	SECPL/E+H/NTPL/21-22/048	W. O. No-	SO/21-22/41
PO Dated :	16-06-21	W. O. Date	25-06-21
PO Received Date:	25-06-21	Sales Co ordinator	Pradeep S
Ref. Quotation:	SQT.18.19.1365R15	Front Sales Person	Vijay Sir

Contact Details		Billing Address:	Dispatch Address:
Site contact 1		C/O Endress+Hauser Flowtec India Pvt Ltd , M-171-176 , Waluj MIDC , Aurangabad-4310136	C/O Endress+Hauser Flowtec India Pvt Ltd , M-171-176 , Waluj MIDC , Aurangabad-4310136
Email ID of contact Person:			
Site contact 2			

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	**Dock Leveler**	Supply and fixing Electro- Hydraulic Dock Leveller of hot deep galvanised steel type radius lip with pair of super bummer of Approved make of - **Size: (W) 2000mm X (H) 3000 mm.** •**Carrying capacity: point load of 6T, UDL of 15T** and Platform with hinged lip made of profiled and anti-slip steel, •**Pair of super bumpers** - 150mm x 80mm x 400mm with heavy steel support, •**Hydraulic power pack** - NIHVA Make suitable for UDL of 15T, According to EN1398 Standred . •**Interlocked** facility provided for sectional door and scissor lift. •**Lip material : Hot Dip galvanised** •**Coating - Hot dip Galvanised** •Travel above & below dock level - (+) 300 / (-) 250 mm •Lip size (W x L) - 2000 x 400 mm •Shut Height - 480mm • **(2 Nos for Phase-I & 2 Nos for Phase -II)**	Nos	4		included	-	**Pending**
2	**Scissor Lift (Pit Mounted)**	**6 Ton Point Load & 15 Ton UDL capacity** electro hydro operated scissor lift of **hot deep galvanised steel (as per IS std),** having **Platform size 2000 mm x 2500 mm** & **lifting height Max. 1200** mm from Ground level to make the system complete in all respects with necessary **Safety Railing of 900mm high all around platform** as per manufacturers specifications including all electrical system units, hydraulic units, controls, connections, **all safety bars**, controls, fittings & accessories required for operations, tools & tackles, labours, machineries etc complete. **Shut Ht - 1000mm** **Max Ht - 2200mm** **Interlocked facility** provided for sectional door and dock leveller. • **Safety Railing in 2 side : Hot Dip Galvanised** • **Manual Lip -Manual Lip - 3 Piece (240 + 1500 + 240) - 1 Side Only** • Power pack sysytem : NIHVA Male Inside the scissor lift Maintenance Stopper - 02 Nos Push Button Pendent - Flexible pendent with 5 mtr Cable - 1 No **Safety Bellow - All side** Hose - Parker Make; Cable - Polycab **(2 Nos for Phase-I & 2 Nos for Phase -II)**	Nos	4		included	-	**Pending**

3	**Automatic Two Leaf Telescopic Sliding Gate**	Clear Opening Size : **(W)6000 x (H)1800 mm** (Total available space as per PO = 8000 mm) • **Two Leaf** Telescopic Gate • Outer Frame : 80 x 80 x 3.2mm MS SQ. TUBE • Inner Frame : 40 x 40 x 2mm MS SQ. TUBE • FOR POST : 80 x 80 x 3.2mm MS SQ. TUBE • GAP BETWEEN INNER TUBES : 100 mm • with European make motor • **Safety : Photocell, flashing light** • Operation - By **Telescopic Mechanism** **Painting - 02 Coats of EPOXY polyamide based enamel finish, RAL -** •**Control Panel - 2 Nos Operating Station(Motor Panel and Security Room)**	Nos	1		included	-	**Pending**
4	**Wicket Gate**	Design, Fabrication, Supply, Installation, Commissioning, packing, transportation to site, furnishing of final drawings and manuals, **handling at site,** erection, commissioning, performance demonstration and performance acceptance etc. of **1.5mx1.8m** size Manual operated swing Wicket Gate of **MS** of approved make with standred tubeler design and **2 Coats of EPOXY polyamide based enamel finish of approved Colour** including all fittings, accessories, locking arrangement from both side . **Clear opening - 1200 x 1800 mm**	Nos	1		included	-	**Pending**

Instructions -
1. Attach PO copy with Invoice
2. Material shalll confirm to IS
3. **Test Certificates are must at the time of delivery**
4. Vehicle must be having its valid documents
5. Insurance to be made by us
6. Drawings and manuals

-

Non standard items/extra requirement, if any:				
B	**Commerical Terms:**			
1	**Payment Terms:**	20% Advance of basic along with P.O and ABG , 75% against delivery of material at site on Pro Rata Basis & 5% After commissionsing & completion. (material delivery payment will be made within 15 days from receipt of material)		
2A	**Delivery Date as per PO:**	8 to 10 weeks from date of P.O and Advance	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	Inclusive	**3B. Transportation Charges:**	NA
4	**P&F Charges:**	NIL		
5A	**Loading Scope:**	NIHVA	**5B. Loading Charges:**	included
6A	**Unloading Scope:**	CLIENT	**6B. Unloading Charges:**	NA
7A	**Lifting Equipments Scope:**	**NIHVA Scope at the time of Installlation**	**7B. Available Lifting Equipments:**	Need to check at site premises
8	**Warranty:**	**24 months from the date of supply.**		
9A	**Height arrangement Scope:**	NA	**9B. Available Equipments for working at Site:**	NA
10	**Electricity Supply:**	CLIENT		
11	**GST:**	Extra -As Applicable		
12A	**Installation Scope:**	NIHVA	**12B. Installation required date:**	-
13	**Mode of import:**	NA		
14	**HSS:**	No		
15	**Documentation Required:**	**MATERIAL TEST CERTIFICATES, INSPECTION REPORTS, MANUALS, WARRANTY CERTIFICATE**		
16A	**Total site visits required:**	-	**16B. Site visit charges:**	-

Certified that the above work order finalised in presence of:

AGM	SALES	Accounts	MFG / Stores	Purchase	PROJECT	DESIGN	Operation	Date & Time
A.K.	**P.S.**	**O.S.**	**R.W. / G.B.**	**A.M.**	**S.M.**	**S.S.**	**V.J**	**26-06-21**