DATE: 07.02.2020

Single Wall Rolling Shutter

SUPPLY & ERECTION OF ROLLING SHUTTER FOR SHAILY ENGINEERING PLASTICS LIMITED, AT HALOL

SR. NO.	DESCRIPTION		UNIT	QUANTITY	UNIT SUPPLY COST IN INR	TOTAL SUPPLY COST IN INR	UNIT ERECTION COST IN INR	TOTAL ERECTION COST IN INR
1	Providing and fixing in position **Motorized** Industrial **Rolling Shutters of Following opening size** without vision panel, suitable for wind peed- 100km/hr conforming to following Specifications : Ref. Drawing No. : 1865-FAC-A01-SH1-A1-R8, SH 1 OF 5,							
A	RS-1 : Opening size - 4000 mm (Wide) x 5000 mm (Hight)		Nos.	1	3,22,000	3,22,000	20,000	20,000
B	RS-2 : Opening size - 5000 mm (Wide) x 6000 mm (Hight)		Nos.	1	4,68,000	4,68,000	20,000	20,000
C	RS-3 : Opening size - 4000 mm (Wide) x 5000 mm (Hight)		Nos.	1	3,22,000	3,22,000	20,000	20,000
D	RS-4 : Opening size - 3500 mm (Wide) x 5000 mm (Hight)		Nos.	1	2,72,000	2,72,000	20,000	20,000
E	RS-5 : Opening size - 2500 mm (Wide) x 2700 mm (Hight)		Nos.	1	2,08,000	2,08,000	20,000	20,000
a.	Opening / Closing Speed	0.05-0.2 m/sec						
b.	Slat Material	Pre-Coated G.I Sheet-Corrugated						
c.	Slat Thickness	1mm Single Wall						
d.	Bottom Profile	GI Bottom Plate with Angle Stiffener with bottom Rubber sealing.						
e.	Side Guide Profile	GI Guides with Rubber insert on both eand.						
f.	Hood cover & motor cover	Galvanised Steel minimum 0.8mm thk. colour coated sheet.						
g.	Paint finishing	Primer + 2 Coats of PU Paint of Approved RAL Shade						
h.	Emergency operation	Manual operation by Hand Crank						
i.	Drive unit	Electric Motor (European Make) Single Phase /Three Phase - bidder to specify tech. data of motor						
j.	Motor	3-phase current 400 V, 50 Hz, protection category IP 54, 60% ED, integral catch safety device, emergency crank handle, cam limit switch (NES), plug-in connections for operator and control wiring Temperature range + 45°C to –0°.						
k.	Push Button	One (1) Push Button on Inside and outside the Factory is required. Total Number-2 No. for each doors.	Set	5	Included			
l.	Flashing Light	One (1) Push Button on Inside and outside the Factory is required. Total Number-2 No. for each doors.	Set	5	Included			
j.	Safety Photocell	One (1) Push Button on Inside and outside the Factory is required. Total Number-2 No. for each doors.	Set	5	Included			
	TOTAL COST					15,92,000		1,00,000
	GST					2,82,240		18,000
	TOTAL COST INCLUDING GST					18,74,240		1,18,000

1. Vendor shall submit the GA drawing of Rolling Shutters with supporting frame structure along with offer submission.
2. Above cost shall be inclusive of all taxes.
3. Above cost shall be inclusive of transporation, insurance, scaffolding and euipments require for erection, etc.
4. Rolling Shutters shall be warranted against defect and performance for a period of 01 years from the date of completion.
5. Bidder to provide technical specifications and price including all applicable taxes etc.
6. Offer shall be inclusive of cable, conduit for cable and cable tray.
7. Welding shall not be allowed at site.
8. All Motors shall be European make.
9. The Quotation Form shall be filled clearly and accurately.
10. Invalid without the seal and signature.
11. Kindly send your Signed and Stamped quotation in sealed cover to following addresses :
Address of Project Site :- **SHAILY ENGINEERING PLASTICS LIMITED,** Near Integra Hindustan Limited, At Village Chandrapura, Ta. Halol, Dist. Panchmahal, Near Vadodara Bidder (seal): Authorized representative (signature): Date: 13.02.2020