NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

DESAI CONSTRUCTION PVT. LTD.
Opp. New GIDC, N. H. No. 48,
Gundlav - 396 035, Dist: Valsad, Gujarat.

Date : 08.02.2020
Quote NO : SQT.19.20.2295R3
Kind Attn : Mr. Yogesh Rohit
Email Id : yogesh.rohit@desaiconstruction.com
Contact No: 9376710357

Project Name & Location: GE, Gandhidham

Subject : Revised Quotation for Motorised Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	MS Motorised Rolling Shutter (Indirect drive)	3850	3600	1	1,24,000	1,24,000	10,000	10,000
2	MS Motorised Rolling Shutter (Indirect drive)	3000	3500	1	96,810	96,810	10,000	10,000
3	MS Motorised Rolling Shutter (Indirect drive)	3000	3600	7	99,576	6,97,032	10,000	70,000
4	MS Motorised Rolling Shutter (Indirect drive)	2000	3000	2	70,910	1,41,820	10,000	20,000
5	MS Motorised Rolling Shutter (Indirect drive)	4000	3660	2	1,31,000	2,62,000	10,000	20,000
			Total Value			**13,21,662**		**1,10,000**
			P&F Charges	3%				
			Total Without Taxes			**13,21,662**		**1,10,000**
			GST Extra @ 18%	18%		2,37,899		19,800
			Total With Taxes			**15,59,561**		**1,29,800**
			Total (Supply + Installtion) with Taxes					**16,89,361**
6	Transportation Charges				**IN NIHVA Scope**			
7	Unloading Charges @ Site				**IN NIHVA Scope**			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications

MS Rolling Shutter

Sr .No.	Specification	Description
1	Rolling Shutter	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of MS Sheet Thickness 0.9 mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Indirect Drive Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection
14	Grill	For 1 Mtr height

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : AT Site

Delivery : 5 - 6 weeks from confirmed purchase order, Advance Payment & Drawing approval.

Payment : For Supply: 20% Advance & balance 80% against readyness before delivery
: For Installation : 100% After Installation

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 18 months from the date of Installation.(Subject to date of installation within one month from date of supply)

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Bhavin Jain on 8551092333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd