NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Bonfiglioli Transmissions Pvt. Ltd
Plot No A–9/5, Phase IV
Village Nighoje, Chakan MIDC, Pune -410 501

Date : 21.10.2020
Quote NO : SQT.20.21.2777
Kind Attn : Mr.Anilkumar Katkam
Email Id : Maintenance.pune@bonfiglioli.com
Contact No: 98506 84494

Project Name & Location: PUNE

Subject : Quotation for Floor Mounted ELECTRO HYDRAULIC Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR		Installation Charges in INR	
		Working Platform (in mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Floor Mounted ELECTRO HYDRAULIC Scissor Lift**	(W) 1000 mm X (L) 1500 mm	1	261,000	261,000	15,000	15,000
			Total		**261,000**		**15,000**
2	P&F Charges on Total Supply Value		3%		**7,830**		
	Total Without Taxes				**268,830**		**15,000**
	GST Extra @ 18%		18%		48,389		2,700
	Total With Taxes				**317,219**		**17,700**
3	Transportation Charges				**In Client Scope**		
4	Unloading Charges @ Site				**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification -

Floor Mounted ELECTRO HYDRAULIC Scissor Lift



Sr. No	Description	Specifications
1	Capacity	1500 Kgs
2	Platform size	(W) 1000 mm X (L) 1500 mm
3	Shut ht	300 mm
4	Max ht	1000 mm
5	Lift ht	700 mm
6	Power pack	3PH 3Phase
7	Safety Railing	on 2 side (900 mm height)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 4 -5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment :80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Amol Gaware on 7758820333.**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd