NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Sandip Khele & Associates
Pune

Date : 13.11.2019
Quote NO : SQT.19.20.2245
Kind Attn : Mr. Sandip Khele
Email Id : sandipkhele@gmail.com
Contact No: **9270113249**

Project Name & Location: Ferrero India, Baramati

Subject : Quotation for Fire Rated Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
3	Fire Rated Rolling Shutter	4000	3000	1	2,44,000	2,44,000	20,000	20,000
				Total		**2,44,000**		**20,000**
4	P&F Charges					**24,000**		
	Total Without Taxes					**2,68,000**		**20,000**
	GST Extra @ 18%			18%		48,240		3,600
	Total With Taxes					**3,16,240**		**23,600**
5	Total with Supply + Installation + Taxes							**3,39,840**
6	Transportation Charges					**In Client Scope**		
7	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Fire Rated Rolling Shutter		
Sr .No.	**Description**	**Specification**
1	Rolling Shutter	Fire Rated Rolling Shutter
2	Shutter Slats	Zinc Coated Steel Slid Slats
3	Slat Thickness	1mm
4	Shutter Guide	Galvanise Steel G65 3 mm Thick
5	Fire mode	Fire shutter will auto close via 71 Degree C Thermal Fusible Link Fire Shutter will auto close by Gravity force when recived 24v Dc fire Signal from control Room fire signal of 24v dc 400mA are required
6	Operated By	Motorise 230volt 50Hz 1P with Manual override chain

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Hemant Sutar 8625089677**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd