NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/16-17/0529 **Date : 02-02-2017**

Swaraj Processing & Systems
Pune, Maharashtra
India

Kind Attn : Mr. Yogesh Patil
Email : swarajprocessandsystems@gmail.com
Contact No :

Project Name And Location :

Subject : Quotation for Telescopic Conveyor

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr	Description	Qty	Unit	Rate In INR	Net Amount INR
1	Telescopic Belt Conveyor (Make - NIHVA) - Belt Width - 600 mm - Fixed length - 2000 mm - Extended length - 4000 mm - Capacity - 50 Kg/ product - Wheels with mechanical arrangement Lock	4	No.s	9,30,000.00	37,20,000.00
	Total				**37,20,000.00**

VAT TIN :	27545250455 V
CST TIN :	27545250455 C
Service Tax No:	AAECN0437HSD001

TOTAL BASIC AMOUNT	**37,20,000.00**
Amount in Words : Rupees Thirty Four Lakhs only.	

Product Image



Technical Specification For Telescopic Belt Conveyor (Make- NIHVA)

Sr.No	Particular	Specification
1	Material To Be Handle	Cable Boxes
2	Weight Of The Box/Bags	50 Kg. maximum
4	Temperature	Ambient
5	Capacity	50 Kg/ Box
6	Type	Telescopic Belt Conveyor
7	Design Capacity	500 per hour
8	Size Of Belt	600 mm Width
9	Type Of Belt	Smooth Top 2 Ply, PVC Coated Endless type
10	Length of conveyor	Fixed length : 2000 mm Telescopic (expanded) : 4000 mm Total : 6000 mm
11	Main Body Of Conveyor	MS tube frame covered with 3mm thick MS sheet material
12	Snub Pulley For Conveyor	Precision Machine from 3 Inch OD Schedule 40 Pipe With Inverted Bearing Fitted
13	Drive Pulley	Manufacture from 8 Inch ID Schedule 40 Pipe With Rubber Legging & hearing bone surface
14	Telescopic Movement	Mechanical arrangement (“Diamond” make chain)
15	Mounting	On Fixed MS Chassis Mounted On fabricated frame with FIX Resting pads.
16	Height Adjustment	With 2 HP power pack & cylinder for height adjustment (“Rexroth” parts) ,(ABB motor)
17	Panel	The conveyor comes with a fixed main panel on rear side and front side only operating panel with emergency stopper sensor bar , LED lighting , totally consoled wiring.
18	Painting	INTERNAL: Two coat of Epoxy red oxide and white paint. EXTERNAL: Two coat of primary & Two coat of high gloss Duco paints.

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material.
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope

2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@3% of Total Supply Value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Sales Tax**	:	Extra as applicable at the time of dispatch. Presently @13.5% VAT (supply withing Maharshtra OR @2% CST against Form C (Outside Maharashtra)
8	**Service Tax**	:	Extra @ 15%
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Mayur Derle** on 7709209333 For any further Clarification /Information in this Concern.

With Best Regards

Monika Kidgaonkar

8551091333

For Nihva Technologies Pvt Ltd