NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Shah Constructions
Marketyard, Pune

Date : 20.10.2020
Quote NO : SQT.20.21.2671 R1
Kind Attn : **Mr.Rajesh Shah**
Email Id : rps0305@gmail.com
Contact No: 9422026643

Subject : Quotation for Supply and Installation of Hangar Door at Pune Airport

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Hangar Door -** Design, Fabrication, Erection and commissioning complete of Hanger Door with motorized system including top frame, top guide, bottom rail, wheels complete.	40000	10500	1	6,455,000	6,455,000	Inclusive	Inclusive
				Total		**6,455,000**		-
			P&F Charges	3%		**193,650**		
			Total Without Taxes			**6,648,650**		-
			GST Extra @ 18%	18%		1,196,757		-
			Total With Taxes			**7,845,407**		-
			Transportation Charges			**Extra at Actual**		
			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Technical details :

Sr No.	Clear Size in mm (W) X (H)
1	(W) 40000 mm X (H) 10500 mm
	Motorized and mechanical opening system for each leaf of door.
	Frame work for whole structure with top and bottom four track r
	Frame work of 08 Nos sliding door shutters with diagonals and cross sections including, wheels complete.
	Welded cladding in each Doors with 0.8mm thick MS Sheets and painted with approved pattern Camouflage painting.
	All Design & Structural Drawing as specified in approved Drawing submitted by the contractor through approved Consulting Agency and as per direction of Garrison Engineer.
	Supply & fix bottom rails sizes as per the design.
	Supply & fix hanger door specification complete all as existing door and as per design
	Hanger door shall be designed as per India standard wind load.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions :

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

Scope of supply

1 The scope includes: Design, production, delivery and Supervision or installation of door & structure.

2 AT client scope (exclusion of NIHVA): Any Civil work, Flooring, Loading and unloading, Transfer of material at site, Lifting Equipments, 3rd party certification, additional PEB sheet, electrical connection, if any

I. Preliminary schedule

1 The schedule below is preliminary. The schedule times will change subject to the final choice of door design. Critical milestones are receipt of the LPO, receipt of the advance payment, final approval of shop drawings, and successful load test of the building and overall site readiness for the door installation.

2 Delivery time: 12-14 Weeks

3 Installation time is subject to site readiness, clear working area and delays by others. Detailed program will be agreed with our project coordinator.

II. Delivery conditions :

Delivery of material will be coordinated with the client written construction schedule. The contractor is responsible for notification to NIHVA of any expected or actual delays in the agreed delivery date at least fourteen (14) days prior to the scheduled delivery. Without timely notification of changes in delivery dates, the contractor or contractor's representative will assume the responsibility of unloading and storing the provided materials in a manner to prevent damage of the materials.

III. Drawings :

We will issue a full set of shop drawings for approval within 2 weeks of receiving the confirmed order and finalized design details

IV. Compensation clause :

Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA compensation of 25% of order value.

General Pre-Requisites Required at Site :

Prerequisites:

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery.

Limit of Supply :

1.Provide place to store the material to be installed.
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation.
4. Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include below:

Client Scope :

1. Once our project gets complete for any additional work to & fro loading &boarding of our service Technicians is in client scope
2.Any civil / masonry/structural work required to support are in client scope.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Terms & Conditions:

Payment	80% advance along with purchase order & balance before dispatch
P & F Charges	3% on supply price
Transport	Extra at actual
Tax	GST @18%
Validity	15 days from the date of offer
Delivery	Within 12 -14 weeks from the date of receipt of confirmed order, drawing approval with advance payment
Insurance	Extra as applicable
Warranty	12 months from date of Supply
Client scope	1. Once our project gets completed; for any additional work to & fro, lodging & boarding of our service technicians is in client scope. 2. Any masonry / structural work required to support are in client scope 3.Lifting equipment's in client scope
Compensation clause	Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA compensation of 25% of order value
Others	Need to provide by client - clear opening mounting structures, any Civil work, electrical points and cables till doors, suitable safe Lifting Equipment's and Scissor lifts, Material and equipment storage secured space, fabrication and assembly space.

General conditions of Aircraft Hangar Door

1. Continuous uninterrupted access to any single door section or as agreed separately.
2. A clear floor area of 4 meters each side of the door leaf must be available during the curtain fitting process. The floor should be finished or if this is not possible, adequate temporary protection be made available to prevent damage to the curtain material.
3. 400 volt / 50Hz 3 phase isolator to be fitted to within 1 meter of the door main control panel. If not available at the start of installation, a temporary supply is acceptable. Any return visits to commission the doors due to permanent power not being available will be charged as appropriate.
4. Provision of 230 Volt power supply (by others) for hand tools.
5. A dry and secure area, not in direct sunlight, is to be provided for storage of the door components.
6. Access to site between 7 am to 6 pm six days per week. If this is not possible the installation programme may require amending.
7. Any storage costs for materials due to delays outside of Mega door's control will be charged to the main contractor.
8. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practices. We reserve the right to extend the period accordingly.
9. Any passes required for the project, are the responsibility of the Customer and Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

Exclusions :

The following items are not within our scope of works and are to be provided by others at no cost to NIHVA
1. Any passes required for the project, are the responsibility of the Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.
2. Power supply and isolators adjacent to the control panels (to be done by electrical contractor).
3. Any Civil work is in client scope.
4. Conduits and Cable trays from the control panel locations to the door distribution boxes, mullion hoist units and door hoist units be provided. (to be done by electrical contractor). These are to be installed prior to the commencement of door installation.
5. A 400/230 power supply (permanent or temporary) must be provided (FOC) by the main Contractor during the installation of the door for power tools and testing of the door sections during erection.
6. A safe storage / pre-assembly area for the door materials (by main contractor).
7. Any additional tests or certification, which are not within our scope of works but may be required by the Consultant or Client, these will be carried out or provided, subject to the actual requirements but will be at additional cost (by main contractor).
8. Lifting Equipment's required for installation.
9. Demolition of concrete floor to lay bottom rails.
10. Material & labour for micro concrete.

Please feel free to Contact Mr. Vijay Tarak on 8551093333 For any further Clarification / Information in this concern.

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd