NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Arun Excello
CHEYYAR SIPCOT -II,
TIRUVANNAMALAI.

Date : 16.11.2019
Quote NO : SQT.19.20.2259
Kind Attn : P.V.Kumaran
Email Id : purchase@arunexcello.com
Contact No: **98403 29701**

Project Name & Location: BEL(BHARAT ELECTRONICS LIMITED) -INFRASTRUCTURE FACILITIES –PALASAMUDRAM,AP

Subject : Quotation for Boom Barrier and Turnstile.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Boom Barrier	6000	1	150,000	150,000	20,000	20,000
2	Single Sided Full Height Turnstile Gate		1	365,000	365,000	20,000	20,000
			Total		**515,000**		**40,000**
3	P&F Charges		3%		**15,450**		
	Total Without Taxes				**530,450**		**40,000**
	GST Extra @ 18%		18%		95,481		7,200
	Total With Taxes				**625,931**		**47,200**
4	Transportation Charges				**Extra**		
5	Unloading Charges @ Site				**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

MICHELANGELO BT A Barrier-1No.(Opening Time- 6S)
• Round Boom First part-1No. • Round Boom Second part- 1 No. • Anchor Base- 1No. • MOB. Boom Rest-1No. • Rubber Safety Profile- 1No. • OMEGA AT Acce. - 1No. • Transmitter with Channels- 1No. • Push Button • Frequency of use- Continuous • Motor Power Supply- 24V

<u>Single Sided Full Height Turnstile Gate:</u> • It has zero position of self -checking, easy for users to maintain and use. • There is alarm notice funtion when illegal access. • Avoid bump funtion: When the turnstile does not receive the open signals, the baffle will lock automatically. • IR/mechanical dual anti-lined funtion: When the baffle has problem in reseng, it will stop working automatic ally in certain time, and the potency is small, will make an alarm sound at the same time. • Resengautomatically: the passenger read effectively, the system will cancel this access authority if they will not access in certain time. • Standard wiring connection: can connect with many kinds of card readers, and can remote control through the computer. • The whole system works steadily, and the noise is very low. lock time: 0.2s; Pass rate: 35 person/min each from both gates; Pass Width: 500-700mm; Input: 100V~240V; Driving Voltage: 24v; Environment: -20~60°c; Power Consumption: 35w; Weight:220kgMake	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Sunny on 8551035333**

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd