NIHVA TECHNOLOGIES

WEIGHT ESTIMATION SHEET

CLIENT	Smith Structure	DATE	22-04-2024
PROJECT	Manual Double Leaf Sliding Door	LOCATION	Pune
FINISH SIZE	8 m x 5.5 m	PREPARED BY	Sumit

SR	DESC	DETAILS	MATERIAL GRADE	SP.GRAVITY	DIA	WIDTH	HEIGHT	THICKNESS	LENGTH	UOM	QUANTITY	WEIGHT	REMARK
1	SINGLE LEAF (4000 mm X 5500 mm)	Tube - Outer Frame	MS	7.85		50	50	3.2	24500	mm	1	115	298
		Inner Tube	MS	7.85		30	30	2.6	14700	mm	1	33	331
		Cladding Sheet	MS	7.86		1200	2500	0.9		mm	9	183	
2	Bottom Track	Guide Bar	MS	7.85	20				16	M	1	39	
		Bottom Side wheel Assembly (4 inch)	MS	7.85					4	No's	4	0	2 wheels to each leaf
		ISMC	MS	7.85		100	50	5	16	M	1	192	
3	Top Track	Guide Track	MS	7.85		100	100	3.2	16	M	1	153	
		Nylon Roller with Bearing			60				60	mm	6	0	2 roller Assly to each leaf
										Weight For Required Qty	1	716	
										Weight Including Safety Factor	1.5	1074	

Mode Of Operation = Manual

REFERENCE IMAGE

