NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

MA Engineering
Pune

Date : 1.10.2020
Quote NO : SQT/20-21/2413R1
Kind Attn : Mr Vittal Pawar
Email Id : vittal.pawar@maengineering.co.in
Contact No: 9823738872

Subject : Quotation for Double Wall Rolling shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorised Insulated Double Wall Rolling Shutter**	5000	4500	1	3,20,000	3,20,000	15,000	15,000
				Total		**3,20,000**		**15,000**
2	P&F Charges			NIL				
	Total Without Taxes					3,20,000		15,000
	GST Extra @ 18%			18%		57,600		2,700
	Total With Taxes					**3,77,600**		**17,700**
3	Transportation Charges				Included in above Prices			
4	Unloading Charges @ Site				Included in above Prices			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification : Motorised Insulated Double Wall Rolling Shutter

Sr. No	Description	Details
1	Size	(W) 5000 mm X (H) 4500 mm
2	Quantity	1 Number
3	Insulation material	Shutter filled with 20 mm thick PU Form
4	Wind load	class 3 (EN 12424)
5	Side Frames:	Aluminium Guide rails with blackplastic runner
6	Bottom profile	Aluminium extruded
7	Power input	1 phase current 0.25kW
8	Protection	IP 65
9	No of Cycles	10 Cycles/hour
10	Safety features:	Bottom Safety edge

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	NIHVA
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : At Site

Delivery : By 26th Oct 2020 from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd