NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0083 **25-12-2017**

Ring Plus Aqua Ltd
D-3/4, STICE , Musalgaon,
Sinnar, Nashik, Maharashtra 422112

Kind Attn : Mr. Abhijit Murkute
Email : abhijeet.murkute@ringplusaqua.co.in
Contact No : 9403099454

Subject : Quotation for Industrial Manipulator

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.

This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
	Manipulator : **1. Manipulator enables the safe and efficient handling of many products up to a maximum weight of 50 kg.** **2. Manipulator incorporates a pneumatic cylinder to achieve the lifting action, and is normally custom buit the relevant working environment** **3. Low noise levels and low maintenance make manipulator the ideal solution for your material handling problems** **4. Three control styles ensure maximum flexibility. Auto balance, powered lift/lower, and pre-set loaded/unloaded options allow the most suitable control style to be used for each handling application.**				
					
A	**Column Mounted Manipulator**	**1**	**No.**	**7,34,000**	**7,34,000.0**
	Manipulator Type : Pneumatic				-
	Manipulator 6 Bar , Capacity : 60 kg				
	Maximum working Radius / Span : 3000 mm				
	Minimum Vertical Lift from Floor : 300 mm				
	Maximum Vertical Lift from Floor : 1300 mm				
B	**Gripper**	**1**	**No.**	**2,20,000**	**2,20,000**
	Application: For lifting Rings				
	Max OD: 1250 mm				
	Min OD: 600 mm				
	Minimum Height : 14 mm				
	Maximum Height : 38 mm				
C	**Installation charges for above system**	**1**	**No.**	**15,000**	**15,000**

GST PUNE :	**27AAECN0437H1ZM**
HSN CODE :	**8428.90.90**

Amount In Words	**Total Amount**	**9,69,000**
	Rupees Nine Lacs Sixty Nine Thousand Only	

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Mahad
2	**P & F Charges**	:	3% Extra as applicable.
3	**Freight Notes**	:	Extra as applicable.
4	**Delivery**	:	8-10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% advance along with confirm Purchase Order & balance before dispatch
6	**Insurance**	:	Extra as applicable.
7	**GST**	:	Extra as Applicable on total supply value.
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre
7709586333
For Nihva Technologies Pvt Ltd