NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ferrero India Pvt Ltd
IMSOFER Division (Unit I) ,Plot No. F-13,
M.I.D.C., Baramati,
Maharashtra, India

Date : 12.03.2021
Quote NO : SQT.20.21.3046R
Kind Attn : Mr.Suhan Shetty
Email Id : suhan.shetty@ferrero.com
Contact No: 02112662294

Subject : Quotation for GI Perforated Motorised Rolling Shutter_ Boiler & Chiller Room , Water Treatment and Compressor Area .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**GI Perforated Motorised Rolling Shutter _Water Treatment Area**	4000	3260	1	150,000	150,000	20,000	20,000
2	**GI Perforated Motorised Rolling Shutter_Compressor Room Door No -1**	3900	3560	1	155,000	155,000	20,000	20,000
3	**GI Perforated Motorised Rolling Shutter_Compressor / DG Room Door No -2**	3800	3580	1	153,000	153,000	20,000	20,000
4	**GI Perforated Motorised Rolling Shutter_Boiler & Chiller Room**	4000	5000	2	195,000	390,000	20,000	40,000
5	**GI Perforated Motorised Rolling Shutter_Boiler & Chiller Room**	3900	5000	1	190,000	190,000	20,000	20,000
			Total			**1,038,000**		**120,000**
	P&F Charges			3%		**31,140**		
	Total Without Taxes					**1,069,140**		**120,000**
	GST Extra @ 18%			18%		192,445		21,600
	Total With Taxes					**1,261,585**		**141,600**
	Transportation Charges					**Extra at actual**		
	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

GI Perforated Motorised Rolling Shutter







Sr. No	Description	Specifications
1	**Rolling Shutter**	Rolling Shutter with GI slat of thickness of 1 mm.
2	**Perforated windows area**	1000 mm Height area middle of total height of shutters
3	**Mounting Location area**	Inside area / Outside area
4	**Curtain Panel**	The panel made of 1 mm thick GI slat
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved with perforation at 0.5 mtr
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GI
12	**Surface finish**	Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5-6 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact me.

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd