NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

GMR Airport Developers Ltd.
Hyderabad

Date : 25.09.2020
Quote NO : SQT.20.21.2688 R
Kind Attn : Divya Odhel
Email Id : Divya.Odhel@gmrgroup.in
Contact No: **8897558787**

Subject : Quotation for Sectional Door, High Speed Door at Pharma Zone Expansion RGIA

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2, 3, 4
C.	General Conditions	5
D.	Terms & Condtions	5

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Sectional Door - ASSA Abloy	5000	5000	1	470,500	470,500	20,000	20,000
2	Sectional Door - ASSA Abloy	7000	5000	1	598,500	598,500	20,000	20,000
3	High Speed Door (NIHVA Make)	5000	5000	1	512,500	512,500	20,000	20,000
3	High Speed Door (NIHVA Make)	7000	5000	1	612,500	612,500	20,000	20,000
4	Clear vision (Transperent) strip curtain of 3 mm thick made of PVC for 7 m (W) x 5 m (H) and 5 m (W) x 5 m (H) opening with 50% overlap with necessary Aluminium channel			110 sq mtr.	1,937	213,070		
5	Removal and Re-installation of existing High Speed Doors including necessary framework, cabling etc complete to ensure Door is functioning			2	30,000	60,000		
	Total for Product (1, 2, 3,4,5)					**2,467,070**		**80,000**
	P&F Charges			3%		**74,012**		
	Total Without Taxes					**2,541,082**		**80,000**
	GST Extra @ 18%			18%		457,395		14,400
	Total With Taxes					**2,998,477**		**94,400**
	Total Supply + Installation with Taxes							**3,092,877**
5	Transportation Charges					**In Client Scope**		
6	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA - Assa Abloy make Sectional Door





Sr. No	Description	Specification
1	Model No	ASSA ABLOY OH1042P
2	Opening Direction & Mounting	Standard
3	Opening/Closing Speed	CDM9 0,28 m/s
4	Door Material	Steel
5	Panel Thickness	42 mm Square Grid, steel sheet
6	Filling	CFC-free polyurethane
7	Door sealent	All door sealants made of EPDM rubber, temperature resistant -30/+70
8	Water Penetration	EN 12425 class 3
9	Air Permealibity	EN12426 class 3
10	Thermal Transittance	EN 12428 1.10W /m2K
11	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
12	Door saftey	Doors equiped with spring break device
13	Incase of Power failuer	Doors to be equiped with quick release fuction
14	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
15	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
16	Emergency Operation	by Disengagement rope manual
17	Operating Switch	Up/Down Keypad + stopbutton
18	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
19	Environmental Green Product Declaration Certification	As per ISO 14025 and EN 15804

NIHVA HIGH SPEED PVC ROLL UP DOOR

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels

Sr. No	Description	Specifications
1	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
2	Opening speed	3 m/s
3	Closing speed	0.8 m/s
4	Control Panel	4 Push Button operated
5	Security Features	EN 13241-1 Standard
6	Resistance to wind load	EN12424 upto class 2
7	Curtain	Fabric Transparent PVC section
8	Guide Material	Aluminum
9	Hood Cover	GI
10	Motor Cover	GI
11	Operator & Control	German Make Motor , VFD
12	Connecting Voltage	220V , 1Ph , N
13	Open-Stop-Close Button	Standarad
14	Protection Category	IP 54 / IP 65
15	Power Consumption	0.75 kw Motor
16	Emergency Off Button	Standard
17	Closing Zone Monitoring	Optical Safety edge
18	External Route Monitoring	Photocell
19	Emergency Opening	Crank Handle
20	Pulll cord Cable and Vision Window	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in Client Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark	
1	Secured and fully covered Store area to keep the material	In Client Scope	
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope	
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope	
4	Any civil / masonry/structural work required	In Client Scope	
5	All structure support required	In Client Scope	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope	
7	Conduits, Cables required	In Client Scope	
8	**Steel structure for Sectional Door**	**In Client Scope**	**If in NIHVA scope of work -Rs. 50000/- extra**

D) Terms & Conditions

Price : Ex works Pune

Delivery : 10 -12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 8551093333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd