NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Lupin Limited
Ghotawade,pirangut

Date : **25.12.2019**
Quote NO : **SQT.19.20.2274R4**
Kind Attn : **Mr. Dheeraj Sawant**
Email Id : dheerajsawant@lupin.com
Contact No: **9833273706**

Subject : Revise Quotation for High Speed Door_High Sea Sale

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1A	**Option 1 : Self Repairable Function Albany Make Rapid Roll Up Door - HS9020G**	2500	3500	3	3,95,000	11,85,000	15,000	45,000
1B	**Option 2 : Non Self repairable Function Albany Make Rapid Roll Up Door - RR300 S**	2500	3500	3	4,30,000	12,90,000	15,000	45,000
				Total				
	P&F Charges			Nil		-		
	Total Without Taxes					-		-
	GST Extra @ 18%			18%		-		-
	Total With Taxes					-		-
6	Transportation Charges					**Included**		
7	Unloading Charges @ Site					**At Nihva Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Option - 1 : Self repairable function

HS9020G




HS9020G



SIDE GUIDES



Safety Facilities



Sr. No	Description	Specifications
1	**Structure**	Galvanized steel
2	**Colours**	8 standard colors - white, yellow, green, orange, red, gray, black, blue
3	**Safety**	• Photocells in side columns • Flexible soft bottom edge including wireless edge activator • Break-away and self-repair function
4	**Operation**	Operator + control unit
5	**Operating speed**	Opening: up to 1,2 m/s (optional 2,0 m/s) ; Closing: 0,5 m/s
6	**Wind load resistance**	Class 1 (300 Pa (N/m²)) maximum wind load while closing 50 N/m²
7	**Air permeability**	Class 1 (24 m³/m²/h at 50 Pa)
8	**Water penetration**	Class 2 (50 Pa (N/m²))
9	**Thermal transmittance**	6,02 W/(m²K)
10	**Lifetime expectations**	1.000.000 cycles
11	**Temperature working range**	5 °C to +40 °C
12	**Vision window**	Horizontal one row of height 400 mm at eye level
13	**Loop Detector for both Side**	6 Set (Only for Metal Detection, for men movement use control pannel button)
14	**Interlock with BMS**	Included (Yes , Only for High Speed Door, for 3 Doors 3 Sets)

B) Technical Specification

Option - 1 : Non - Self repairable function


RR300 S



RR300 S



Motor and Control Panel



Color options

Sr. No	Description	Specifications
1	**Structure**	Galvanized steel
2	**Colours**	8 standard colors - white, yellow, green, orange, red, gray, black, blue
3	**Safety**	• Electrical safety contact edge • door line photocell
4	**Operation**	Operator + control unit
5	**Operating speed**	Opening: up to 2.3 m/s ; Closing: 1.0 m/s
6	**Wind load resistance**	class 1 (EN 12424).
7	**Bottom Profile**	Anodized Aluminum
8	**Protection**	IP55
9	**Control System**	Frequency converter control system MCCVectorControl, based on vector control including boost function at start-up. Graphic display and foil keypad for easy guided operation. Easy access to all important information regarding operation and service
10	**Supply voltage:**	3L(N)PE/380/400/415/440/480V;50/60Hz
11	**Loop Detector for both Side**	6 Set (Only for Metal Detection, for men movement use control pannel button)
12	**Interlock with BMS**	Included (Yes , Only for High Speed Door, for 3 Doors 3 Sets)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Above prices are CIF prices by Sea which are without any custom duty, clearance and Taxes.
2. There will be High Sea Sales agreement between NIHVA and Lupin Ltd, this is to signed by both parties before arrival of equipment at Seaport
3. Since this is Sea consignment both the parties will have to take at most care during this transaction as the agreement is required to discharge in between the period of dispatch and receipt at sea port
4. For any reason if consignment gets hold at custom NIHVA will not be responsible for any delayed charged or penalty.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	**Custom Duty + Custom Clearance, till site in clients Scope. NIHVA will handover BL to client for further all process & action till material reaches at site & unloads at required place.**	In Client Scope
2	Secured and fully covered Store area to keep the material	In Client Scope
3	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	NIHVA
4	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
5	Any civil / masonry/structural work required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : CIF Mumbai (High Sea Sale)

Delivery : 12-13 Weeks for High Speed Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333.**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd