NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

John Deere India Pvt Ltd
Sanasawadi
Pune - 412208

Date : 14.03.2020
Quote NO : SQT/19-20/2498
Kind Attn : Mr. Narayan Pawashe
Email Id : PawasheNarayan@JohnDeere.com
Contact No: 8805150435

Subject : Quotation for ASSA ABLOY Make High Speed Door for Internal Application

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Option 1 : High Speed Door RR300+ Al**	3000	4000	1	676,000	676,000	15,000	15,000
2	**Option 2 : High Speed Door HS9020G**	3000	4000	1	674,000	674,000	15,000	15,000
			Total					
3	P&F Charges			NIL				
	Total Without Taxes				-		-	
	GST Extra @ 18%			18%	-		-	
	Total With Taxes				-		-	
4	Transportation Charges				Included in above Prices			
5	Unloading Charges @ Site				NIHVA Scope			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Option 1 - RR300+ Al **High Speed Door RR300+ Al**



Sr. No	Description	Details
1	Size	(W) 3000 mm X (H) 4000 mm
2	Quantity	1 Number
3	Door panel:	Transparent PVC with Red (RAL 3002) reinforcement stripes.
4	Barrel:	Aluminium, anodized with shafts made of galvanized steel
5	Wind Reinforcement:	Door Panel wind tabs for improved wind resistance
6	Side Frames:	Aluminium profiles, anodised
7	Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
8	Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.
9	Bottom beam:	Anodized extruded aluminium.
10	Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s
11	Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns

Option 2 : HS9020G **High Speed Door HS9020G**



Sr. No	Description	Details
1	Size	(W) 3000 mm X (H) 4000 mm
2	Quantity	1 Number
3	Structure	Galvanized steel
4	Colours	8 standard colors - white, yellow, green, orange, red, gray, black, blue
5	Safety	• Photocells in side columns • Flexible soft bottom edge including wireless edge activator • Break-away and self-repair function
6	Operation	Operator + control unit
7	Operating speed	Opening: up to 1,2 m/s (optional 2,0 m/s) ; Closing: 0,5 m/s
8	Wind load resistance	Class 1 (300 Pa (N/m²)) maximum wind load while closing 50 N/m²
9	Air permeability	Class 1 (24 m³/m²/h at 50 Pa)
10	Water penetration	Class 2 (50 Pa (N/m²))
11	Thermal transmittance	6,02 W/(m²K)
12	Lifetime expectations	1.000.000 cycles

13	Temperature working range	5 °C to +40 °C
14	Vision window	Horizontal one row of height 400 mm at eye level

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	NIHVA
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : At Site

Delivery : 12 - 14 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd