<table>
<tr><th>S.NO</th><th>Parameters</th><th>Description</th><th>Remark</th></tr>
<tr><td></td><td></td><td></td><td></td></tr>
<tr><td>1</td><td>Application</td><td>Pick & place of sheet metal component from die press</td><td></td></tr>
<tr><td>2</td><td>Box Erector & tapping line</td><td>Design Components:
<table>
<tr><td>S.no</td><td>Component</td><td>Application</td></tr>
<tr><td>1.</td><td>Moving Track</td><td>Track to guide trolley</td></tr>
<tr><td>2.</td><td>Trolley</td><td>Moving trolley to hold suction system</td></tr>
<tr><td>3.</td><td>Motor system</td><td>Motor to move suction cup system</td></tr>
<tr><td>4.</td><td>Control panel</td><td>To control the system</td></tr>
</table></td><td></td></tr>
<tr><td>6</td><td>Control Panel & Its Basic Features</td><td>Cabinet:
1. Main control panel : Floor / machine mounted cabinet
2. Approx size: 1000(L) X 700(W) X 300(H)
Switch Gear:
1. Main Isolation through MCCB.
2. Interlocks through main contractor
Junction box:
Cabinet cooling : Fans are provided for cabinet cooling</td><td></td></tr>
<tr><td></td><td>PLC & Automation</td><td>1. Seimens PLC is used for automation control.
2. 4” HMI for Control input & alarm display</td><td></td></tr>
<tr><td></td><td>Components & Make list.</td><td>Only reputed bought-out components are used. The price is worked out on the basis of make list provided. Any other makes other than this should be mentioned prior to order so than final price & delivery schedule can be concluded.
<table>
<tr><th>Components</th><th>Make</th></tr>
<tr><td>Control Panel Cabinet</td><td>M.S cabnite</td></tr>
<tr><td>MCB</td><td>Siemens</td></tr>
<tr><td>Indicator Lamps, selector switch & push buttons</td><td>Technik</td></tr>
<tr><td>Wires inside control Panel</td><td>Finolex / Polycab</td></tr>
<tr><td>Terminals in control panel</td><td>Connectwel/ Wago</td></tr>
<tr><td>PLC</td><td>seimens</td></tr>
<tr><td>HMI</td><td>4” HMI, seimens</td></tr>
<tr><td>Isolation Transformer</td><td>NANAP/AE</td></tr>
<tr><td>Relay</td><td>Omron/ Phoenix</td></tr>
<tr><td>Cooling Fans</td><td>Sunon</td></tr>
<tr><td>VFD</td><td>seimens</td></tr>
<tr><td>Power Supply</td><td>Omron</td></tr>
</table></td><td></td></tr>
<tr><td></td><td></td><td>Customer’s scope:</td><td></td></tr>
</table>

	Cables & its Scope of supply	1. All Cables from control panel to terminal box will be in Customers scope. **Supplier's Scope:** 2. Cables from terminal box to system maximum up to 4mts will be provided. Cable schedule will be provided after order finalization.	
7	**Final Testing**	Final Pre dispatch inspection will be offered. this will be done on the basis of Validation sheet mutually agreed at the time of GA approval	
8	**Delivery schedule**	The delivery schedule begins after the receipt of order. **Delivery will be 4-6 weeks.**	
9	**Documentation**	1. All G.A. Drawings & validation sheet will be provided. 2. Electrical diagrams and mechanical diagrams will be as per DIN standards. 3. Two sets of hard copy of operating manual will be provided at the time of dispatch.	
10	**Packing & Transportation**	**Packing:** customer scope **Transportation scope**	
11	**Installation and Commissioning & Training**	**Separate quotation will be provided.** Our commissioning Engineer will explain entire control panel functionalities and the manual. This may take about 1-2 days	
12	**Warranty**	The equipment is guaranteed against any manufacturing defects for a period of 12 months from the date of control panel commissioning or 16 months from the date of delivery.	
13	**Exclusion from warranty**	1. The warranty does not cover normal wear and tear. 2. Defects arising out of breakage and mishandling are excluded from this warranty.	
14	**Post warranty Service**	We recommend our AMC (Annual Maintenance Contract) service after warranty period.	
This Quotation is valid for 6 month only.			