NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

JLL
Bund Garden Road Pune

Date : 10.09.2019
Quote NO : SQT.19.20.2047
Kind Attn : Mr. Saurabh Samrat
Email Id : saurabh.samrat@ap.jll.com
Contact No: **7038208190**

Project Name & Location: JLL India, Pune

Subject : Quotation for High Speed Clean Room Door RR300 Clean

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA ASSA ABLOY High Speed Door RR300 Clean**	1500	2100	1	7,08,000	7,08,000	20,000	20,000
				Total		**7,08,000**		**20,000**
2	P&F Charges			3%		**21,240**		
	Total Without Taxes					**7,29,240**		**20,000**
	GST Extra @ 18%			18%		1,31,263		3,600
	Total With Taxes					**8,60,503**		**23,600**
3	Transportation Charges					**In Client Scope**		
4	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Door construction:	Certified flexible high performance door, opening in vertical direction, certified for the use in cleanrooms. Compliant to the national norms and regulations in cleanroom applications according to DIN EN ISO 14644-1 and GMP. Certified according to ISO 5 and GMP class C. Low Particle emission , Low Air Exchange. Certified by Fraunhofer
Lintel space requirement:	410mm Minimum
Control system incl. self-opening:	Frequency converter control MCC VectorControl with uninterrupted power supply (UPS) for continuous operation in case of power failure. UPS and MCCVectorControl are installed under the top roll cover. Graphic display and foil keypad for easy operation installed on the drive side.
Door curtain:	Made of PVC with vertical reinforcement stripes in white (similar RAL 9016).
Speed:	2.0 / 1.0 m/s
Power supply:	3L/(N)PE 380/400/415/440/480V; 50/60 Hz.
Safety device:	Pre-running photocell, door line photocell integrated in the side frames, drop down protection in the drive unit.
Protection:	IP 55.
Self-supporting side frames made of stainless steel V2A:	Self-supporting side frames max. DW 110 mm, motor cover , top roll cover & bottom profile are in Stainless Steel V2A .
Actuators / Switch:	Integrated, contactless actuator mounted on Guide rail / side frame.
Drive unit:	Direct Drive Gear motor, mountable left or right.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd