NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Gupta Packaging
Ghaziabad, Delhi

Date : 7.12.2020
Quote NO : SQT.20.21.2869
Kind Attn : Deepak. Gupta
Email Id : d.deepakgupta91@gmail.com
Contact No: 9441157672

Project Name & Location: Ghaziabad, Delhi

Subject : Quotation for Commercial Goods Lift .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Depth (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Commercial Goods Lift**	1500	1350	1	2,125,000	2,125,000	20,000	20,000
				Total		**2,125,000**		**20,000**
2			P&F Charges	3%		**63,750**		
			Total Without Taxes			**2,188,750**		
			GST Extra @ 18%	18%		393,975		-
			Total With Taxes			**2,582,725**		-
3			Transportation Charges			**Extra at Actual**		
4			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Commercial Goods Lift		
SR NO	**DETAILS**	**SPECIFICATION**
1	Capacity	2000kg
2	Speed	0.25m/s
3	Car Travel	G+4 floor
4	No of stops	Three stops
5	No of openng	Three openings (all openning on the same side)
6	Drive	V3F Drive with synchronization
7	Main power supply system	415 volts, 3 phase, 50 hz a.c. (client scope)
8	Light supply	230 volts, single phase 50 hz a.c. (client scope)
9	Machine	Hydraulic Traction Machine
10	Landing door finish	Manual Swing Door
11	Car door finish	Manual Collapsible Door
12	Door openning	1200 mm clear door openning
13	Car size	1500mm width and 1350mm depth (size can be changes as per gad)
14	Car finish	Mild Steel Powder Coated (made by high quality pre coated sheet)
15	Car flooring	M.S.Plate
16	False Ceiling	Mild Steel Powder Coated
17	Hand rail	Optional
18	Elevator rope	Usha Martin (dual strength)
19	Elevator well	2000 mm width,2000 mm depth (inside finished)
20	Machine room	As per required
21	Elevator pit	1500 mm depth
22	Speed governor	NA
23	Fireman option	NA
24	Control system	Simplex down collective control panel
25	Controllertype	Microprocessor base control panel
26	Signals	1) up/down direction indicators with operating panel at all landing
		2) digital car position indicators and operating panel inside the cabin

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9-10 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd