NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Dell'Orto India pvt ltd
Chakan, Pune - 560105

Project, Location :

Date : 21.09.2021
Quote NO : SQA.21.22.0224
Kind Attn : Bhupen. Dorle
Email Id : bhupen.dorle@dellortoindia.in
Contact No: 9850241110

Subject : Quotation for Pit Mounted Hydraulic Scissor Lift - 2 Ton

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Lenght (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Pit Mounted Hydraulic Scissor Lift - 2 Ton Total Height - 2400 mm**	1400	2100	2	482,000	964,000	15,000	30,000
2	**Pit Mounted Hydraulic Scissor Lift - 2 Ton Total Height - 1800 mm**	1400	2100	2	403,000	806,000	15,000	30,000
	Total			**4**		**1,770,000**		**60,000**
3	P&F Charges			3%		53,100		
	Total Without Taxes					1,823,100		60,000
	GST Extra @ 18%			18%		328,158		10,800
	Total With Taxes					**2,151,258**		**70,800**
4	Transportation Charges					Extra at atcual		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad. Pune – 411019

An ISO 9001:2015 Certified Company
GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Pit Mounted Scissor Lift

Sr. No	Description	Specifications
1	**Capacity**	2 ton
2	**Platform size**	1400(W) x 2100 (L)
3	**Shut ht**	600 mm
4	**Max ht**	1800 mm & 2400 mm
5	**Lift ht**	1200 mm & 1800 mm
7	**Safety Railing**	both length side only (900 mm height)
8	**Color**	as per req. RAL shade.
9	**Lip**	Manual Lip on one side
10	**Hyd Cylider - Seal kit (Rod end , Head end & Piston)**	Standard
	Hydraulic power pack	3HP, 3 Phase
1	**Gear Pump**	Make Rexroth
2	**ele. Motor**	Siemens / Equivalent
3	**Valves**	Rexoth / Yuken / Equivalent
4	**Saftey**	special pilot op check valve
		Manual stand used during Maintainence purpose
		adjustable Limit Switches
5	**Hose**	Standard
6	**Controls**	UP, DOWN and Emergency stop controlled through push buttons provided outside the platform. The lift shall stop automatically , when the platform reaching the desired floor level by actuation of pre adjusted levelling limit switches.
7	**Electrical System**	The continuous running powe pack unit with specified motor starter with suitable length cables. The cylinder unit shall be provided with limit switch and push button control with panel board. The electric panel will have starter contactors, MCB's, push buttons, limit switches and terminal strip. The control panel/cabinet have a seprate stand.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune
Delivery : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity : Validity of Offer is 15 days from the date of quotation
Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd