Sales Quotation

Quotation No. SQT/19-20/2096R **Date: 03/10/2019**

OSS Air
Delhi
India

Kind Attn: Mr. Suraj Pandey
Email: suraj.pandey@ossair.com
Contact No: 09871461393

Project Name and Location: Pune

Subject: Modification/Installation of Electrically operated Sliding Hangar Door.

Dear Sir,

Thank you for your visit to our office on 18.09.2019. With reference to the meeting and our subsequent site visit we would like to state our observations and suggestions as follows.

1. The orientation of the doors needs to be reversed for positive and appropriate closure. This arrangement will ensure accommodation of all the door panels within the assigned side pocket areas and will eliminate the requirement of additional enclosures on the sides.

2. The bottom reinforcement needs to be corrected accordingly.

3. For facilitating the smooth ingress and egress of the helicopter through the door, we will provide recessed tracks on this corrected bottom reinforcement. This arrangement will also eliminate the large gap at the bottom of the doors and therefore there will be no need to provide any bottom seals.

4. As discussed, we will arrange provision of the load analysis and load test certificate through competent agencies. This will attract additional cost which is indicated in our proposal.

5. A detailed work schedule is also attached for your reference

While on the subject we would like to reinstate that considering the site and the type of helicopter that will be housed inside this hangar, it is always recommended to use vertical lifting hangar doors instead of horizontal sliding door.

Regards

Varsha

8551091333

NIHVA TECHNOLOGIES PVT LTD

Size of the door: 22 M (W) X 6.5 M (H)

Commercial Offer:-

Sr No.	Description	Qty (No'S)	Amount (INR)
1	**Modifications to be done** • Reversal of orientation of door panels and correction of the bottom structural support to suit this requirement. • Bottom ISMB provision and installation with recessed tracks • Top rail (ISMB) structure and tracks • Lateral ISMB installation on top, fabricate with existing structure & maintain distance from bottom rail. • Painting • Vertical door Seals for all panels	1	14,45,429
2	Design analysis and load test	1	3,48,571

Note: For any reason if we are asked / required to stop work while installation is in progress then there will be an extra cost per day per person around Rs 4,500.

General Pre-Requisites Required at Site

Prerequisites:

1. Finished flooring after curing (without water)

2. Single phase / three phase power supply with necessary plug points in the vicinity of the work area suitable to connect power tools and welding equipment.

Scope of work

- Pre-installation inspection by our Project Manager, before our installers reach the site, to ensure site readiness.

- Lifting Equipment (Boom Lift / Scissor Lift, Crane Structure modification & Consumables

- Installation of the Door Structure, door leaves, door rails, motors, control panel and electrical wiring.

- Our scope is limited to the necessary modification of the door that is available at site. We will use the available door panels and related accessories to installation it and to operate it.

- The work will be carried out in strict adherence to the drawing and any deviation / modification out of this scope will be charged extra.

Terms & Conditions:

Payment	**Installation Payment:** 1. Mobilization Advance 30% along with PO. 2. 30% payment after installation of top and bottom supports 3. 30% payment after installation of door panels 4. 10% payment after making the door operational **Supply Payment: 100% after receipt of Material at Site (Before Installation)**
Tax	GST @ 18% Extra
Warranty	Service Warranty of 12 Months from Date of Installation **Note:** Warranty is only applicable on Door Installation, if the door stops working due to any product or component failure, then NIHVA is not responsible for the warranty.
Validity	15 days from the date of offer
Installation Time	30-40 Days after formal work order, release of advance or site readiness; whichever is later
Compensation clause	In case of an eventuality of cancellation of the order for any reason beyond our control, the customer is liable to pay a cancellation fees of 25% of the order value within 15 days of the cancellation
Provisions by the customer	• A clear opening mounting structure needs to be provided • All required civil work for bottom track, top track and etc…wherever needed • Front cladding on the door panels • A covered weather proof storage facility in the vicinity of the work area • Provision of space for fabrication & assembly in the vicinity of the work area • Arrangement of necessary permissions and access to the site • Single phase or three phase power supply with necessary plug points in the vicinity of the work area. • The door panels and its related hardware.

Please feel free to Contact Mr. Arjun Patil on 08551096333 For any further Clarification / Information in this concern.

Regards
Varsha
8551091333
NIHVA TECHNOLOGIES PVT LTD