Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.1663 R **Date: 07/01/2019**

Knight Frank (India) Pvt. Ltd

Unit No. 407 & 408, 4th Floor, Block-C, 'The First', Behind ITC Hotel Near
Keshav Baug Party Plot, Vastrapur
Ahmedabad - 380015
Gujarat -India

Kind Attention: Mr. Tushar Urade

Phone:- +91 97129 43313
Email ID: tushar.urade@in.knightfrank.com

Project Name And Location :

Subject : Quote for -Motorised Rolling Shutter, Sectional Doors and High Speed Doors

Dear Sir,

Thank you for your opportunity and trust shown on “NIHVA.” your preferred partner for innovative solutions.This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer :-

Sl.No.	Description	Price	Qty	Unit	Total
1.	Double Wall Motorised Rolling Shutter - Direct Drive Size :(W) 4000 mm x (H) 4000 mm Technical Specifications : • Direct Drive • PCGI Slat : 19 mm Thick • Profile : Curved Type Profile with heavy duty Shaft • Guide : M S Guide • Hood Cover & Motor Cover : GI Powder Coated • With Push Button and Flashing Light (Supply + Installation)	₹ 365,000.00	2	Nos	₹ 730,000.00
2.	ASSA ABLOY Make Motorized Sectional Door 100 % Imported from Europe Specifications : Lifting : Standard Lift Windows : 2 nos. Accessories : Motor and Control with all safety features Extra Push Button, Remote and Receiver Size : (W) 6000 mm x (H) 7500 mm (Supply + Installation)	₹ 1,332,000.00	6	Nos	₹ 7,992,000.00
3.	ASSA ABLOY Make Motorized Sectional Door 100 % Imported from Europe Specifications : Lifting : Standard Lift Windows : 2 nos. Accessories : Motor and Control with all safety features Extra Push Button, Remote and Receiver Size :(W) 4000 mm x (H) 4000 mm (Supply + Installation)	₹ 468,000.00	2	Nos	₹ 936,000.00
4.	High Speed Door RR392 100% Imported with all components – made in Germany High-Speed Roller Door : Curtain RollTex Plus blue (RAL 5002), orange (RAL 2009) or grey (RAL 7001) without window. Door with curtain tension. Safety Features : Safety contact edge, Safety photocell transmitter / receiver inside side columns. Size : (W) 4000 mm x (H) 4000 mm (Supply + Installation)	₹ 788,788.00	3	Nos	₹ 2,366,364.00
5.	High Speed Door RR392 100% Imported with all components – made in Germany High-Speed Roller Door : Curtain RollTex Plus blue (RAL 5002), orange (RAL 2009) or grey (RAL 7001) without window. Door with curtain tension. Safety Features : Safety contact edge, Safety photocell transmitter / receiver inside side columns. Size : (W) 3000 mm x (H) 3000 mm (Supply + Installation)	₹ 733,100.00	5	Nos	₹ 3,665,500.00
6.	High Speed door HS8010P ASSA ABLOY make High Speed Door - HS8010P Suitable for Outside operation Operating speed : opening: up to 2,4 m/s closing: 1,2 m/s Wind load resistance EN 12424 : class 3 (700 N/m2) ,class 4 (1000 N/m2) Water penetration, EN 12425 : class 2 (50 N/m2)	₹ 888,549.00	3	Nos	₹ 2,665,647.00

Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.1663 R					Date: 07/01/2019
Sl.No.	**Description**	**Price**	**Qty**	**Unit**	**Total**
	Size : (W) 4000 mm x (H) 4000 mm (Supply + Installation)				
7.	High Speed door HS8010P ASSA ABLOY make High Speed Door - HS8010P Suitable for Outside operation Operating speed : opening: up to 2,4 m/s closing: 1,2 m/s Wind load resistance EN 12424 : class 3 (700 N/m2) ,class 4 (1000 N/m2) Water penetration, EN 12425 : class 2 (50 N/m2) Size : (W) 3000 mm x (H) 3000 mm (Supply + Installation)	₹ 808,582.00	5	Nos	₹ 4,042,910.00

Sub Total	₹ 22,398,421.00
Grand Total	**₹ 22,398,421.00**

GST Pune	27AAECN0437H1ZM

General Pre requisite at site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required
5 Scaffolding require for Installation it is in client scope

Limit of Supply

1 Provide place to store the material to be installed
2 Be responsible for the safe custody of all material
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel

Client Scope

1 Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Existing/Repair/ Modification/ Refurbishment charges will be extra

Terms & Conditions

1 **Price** : Ex works Pune
2 **P & F Charges**: @3% of Total Supply Value
3 **Freight Notes**: Extra as applicable
4 **Payment**: 80% Advance along with confirm purchase order & Balance 20% before dispatch
5 **Taxes**: GST @ 18%
6 **Validity**: Validity of Offer is 15 days from the date of quotation.
7 **Warranty**: 12 months from the date of supply
8 **Delivery** : 12-14 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
9 **Insurance :**Extra As applicable

Please feel free to Contact **Mr. Arjun Patil on (855) 109-6333** for any further Clarification /Information in this Concern.

With Best Regards

Smita Khare
+91-9637991333
For Nihva Technologies Pvt Ltd