NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ferrero India Pvt Ltd
IMSOFER Division (Unit I) ,Plot No. F-13,
M.I.D.C., Baramati,
Maharashtra, India

Date : 22.02.2021
Quote NO : SQT.20.21.3046
Kind Attn : Mr Tausif Shaikh
Email Id : tousif.shaikh@ferrero.com
Contact No: 7722023571

Subject : Quotation for Assa Abloy Make Sectional Door _ Water Treatment and Compressor Area .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**ASSA ABLOY Make Sectional Door-OH1042P STD Lift_Water Treatment Area**	4000	3600	1	330,000	330,000	20,000	20,000
2	**ASSA ABLOY Make Sectional Door-OH1042P STD Lift_Compressor Room Door No -1**	3960	3700	1	330,000	330,000	20,000	20,000
3	**ASSA ABLOY Make Sectional Door-OH1042P STD Lift_Compressor Room Door No -2**	4000	3700	1	330,000	330,000	20,000	20,000
			Total			**990,000**		**60,000**
	P&F Charges			3%		**29,700**		
	Total Without Taxes					**1,019,700**		**60,000**
	GST Extra @ 18%			18%		183,546		10,800
	Total With Taxes					**1,203,246**		**70,800**
4	**Transportation Charges**					**Extra at actual**		
5	**Unloading Charges @ Site**					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA ABLOY Make Sectional Door-OH1042P STD Lift

Sr. No	Description	Specifications
1	Day Light Width (DLW)	4000
2	Day Light Height (DLH)	3600
3	Total height floor to ceiling	4085
4	Enter Headroom	485
5	Minimum required headroom	485
6	Minimum required depth	4200
7	Minimum required sideroom left	270
8	Minimum required sideroom right	132
9	Door Weight	164
10	Calculated U-Value [W/m²K]	1.2
11	Number of panes	4
12	No of windows	4
13	Door panel finish	Pre-coat Steel panel as noted below
14	Shop Painted Colour Outside	Pre coat RAL 9002 Grey white
15	Panel Colour Inside	Pre coat RAL 9002 Grey white
16	Horizontal Track Inclination	0
17	Min. load changes	20000
18	Windload Class	Class 3
19	Track Length L3 [mm]	3466
20	Number of stacked shafts	1
21	Position of Lock	LOCK LEFT
22	Section with Lock	2
23	Operator	CDM9 Single phase 230 volt motor unit
24	Recommended control cable length	3300
25	Type of track	6
26	Horizontal minimum depth (wall to end of track)	4200

Sr. No	Description	Specifications
1	Day Light Width (DLW)	4000 / 3960
2	Day Light Height (DLH)	3700
3	Total height floor to ceiling	4185
4	Enter Headroom	485
5	Minimum required headroom	485
6	Minimum required depth	4300
7	Minimum required sideroom left	270
8	Minimum required sideroom right	132
9	Door Weight	168
10	Calculated U-Value [W/m²K]	1.2
11	Number of panes	4
12	No of windows	4
13	Door panel finish	Pre-coat Steel panel as noted below
14	Shop Painted Colour Outside	Pre coat RAL 9002 Grey white
15	Panel Colour Inside	Pre coat RAL 9002 Grey white
16	Horizontal Track Inclination	0
17	Min. load changes	20000
18	Windload Class	Class 3
19	Track Length L3 [mm]	3566
20	Number of stacked shafts	1
21	Position of Lock	LOCK LEFT
22	Section with Lock	2
23	Operator	CDM9 Single phase 230 volt motor unit
24	Recommended control cable length	3400
25	Type of track	6
26	Horizontal minimum depth (wall to end	4300

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10-12 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Amol Gaware on 7758820333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd