Sales Quotation

Quotation No - SQT/19-20/1500 **Date : 19-04-2019**

Creative Turnkey Projects Pvt Ltd
Office No. 8, Spandan, Above State Bank of India,
Opp. Mai Mangeshkar Hospital,
Mumbai-Bengluru Bypass, Warje, Pune - 411 058

Kind Attn : Mr. Satish Jadhav
Email : purchase@ctppl.com
Contact No : +91 8087026744

Project Name And Location : Wallmart Tirupati

Subject : Quotation for Motorised Rolling Shutter.

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**NIHVA Make Motorized Rolling Shutter** **HSN Code: 73083000** **• GI Slat:1 mm Thk,** **• Curved Type Profile with heavy duty Shaft, Guide** **• Hood Cover 0.9 mm thick** **• Motor - Indirect Drive** **• Inclusive of painting** **Supply + Installation**				
1	Size : (W) 3000 mm x (H) 3000 mm	1	No	101,900	101,900
2	Size : (W) 3050 mm x (H) 3050 mm	1	No	103,500	103,500
3	Size : (W) 3050 mm x (H) 3600 mm	3	No	115,700	347,100
4	Size : (W) 1800 mm x (H) 1200 mm	1	No	65,500	65,500
5	Size : (W) 2400 mm x (H) 3000 mm	2	No	92,900	185,800
				Total	**803,800**

GST Pune	27AAECN0437H1ZM

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in Client Scope

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex works NIHVA Factory
2	**P & F Charges**	:	@3% of Total Supply Value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with order ,balance before dispatch
6	**Insurance**	:	Extra as applicable
7	**Tax**	:	GST Extra @ 18%
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 07410196333** For any further Clarification / Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd