NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Škoda Auto Volkswagen India Private Limited
Aurangabad

Project, Location : Aurangabad

Date : 05.03.2021
Quote NO : SQT.20.21.3042R
Kind Attn : Mr.Nilesh Khandare
Email Id : nilesh.khandare@skoda-vw.co.in
Contact No: 9373844477

Subject : Quotation for High Speed Doors - HS 8010PL

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**ASSA ABLOY High Speed Door - HS8010PL with Radar on both side, Interlocking, Remote Control, Structure Modification, Scafolding (HALL C - VESTIBULE)**	5970	4000	1	1,394,000	1,394,000	Inclusive	
2	**ASSA ABLOY High Speed Door - HS8010PL with Loop Detector, Radar, Interlocking, Remote Control, Structure Modification, Scafolding (HALL C - VESTIBULE)**	5715	4000	1	1,396,000	1,396,000	Inclusive	
3	**Removing of Existing Sectional Overhead Door**			2	25,000	50,000		
	Total			**4**		**2,840,000**		**-**
4	P&F Charges			0%		-		
	Total Without Taxes					2,840,000		-
	GST Extra @ 18%			18%		511,200.00		-
	Total With Taxes					**3,351,200**		**-**
5	Transportation Charges					Inclusive		
6	Unloading Charges @ Site					Inclusive		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA ABLOY High Speed Door - HS8010PL



Sr. No	Description	Specifications
1	Structure	Galvanized steel
2	Colours	8 standard colors - white, yellow, green, orange, red, gray, black, blue
3	Safety	• Photocells in side columns • Flexible soft bottom edge including wireless edge activator • Break-away and self-repair function
4	Operation	Operator + control unit
5	Operating speed	opening: up to 1,4 m/s ; closing: up to 0,6 m/s
6	Wind load resistance	class 3 (700 N/m2) class 4 (1000 N/m2) for doors up to 6000 x 5500 mm
7	Air permeability	Class 1 (24 m3/m2/h at 50 Pa) EN 12426
8	Water penetration	class 1 (30 N/m2)
9	Thermal transmittance	6,02 W/(m2K)
10	Performance Test	750.000 cycles
11	Temperature working range	0 °C to +40 °C
12	Vision window	Horizontal one row of height 400 mm at eye level

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd