NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Azad Rolling Shutter and Construction
Mohan Cinema Road, Opp. J. P. Market
Kota - 324 006 (RAJASTHAN)

Date : 27.01.2021
Quote No : SQT.20.21.2975R
Kind Attn : Mohammed Imran
Email Id : azadrollingshutter@yahoo.co.in
Contact No: 9828137864/9828384287

Project Name & Location: Bhutan

Subject : Quotation for 4 Hrs Fire Rated Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**4 Hrs Fire Rated Rolling Shutter**	6150	9150	7	896,000	6,272,000	20,000	140,000
2	**4 Hrs Fire Rated Rolling Shutter**	2500	2350	2	200,000	400,000	20,000	40,000
				Total Value		**6,672,000**		**180,000**
				P&F Charges	3%	200,160		
				Total Without Taxes		**6,872,160**		**180000**
				GST Extra @ 18%	18%	1,236,989		32400
				Total With Taxes		**8,109,149**		**212400**
3				Transportation Charges		**Extra at Actual**		
4				Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications





4 Hrs. Fire Rated Rolling Shutters - 100% IMPORTED

- **Shutter Slats: SKB-A7 -Zinc Coated Solid Slats Powder Coated to RAL colour manufacturer std**
- **Slat Thickness: 1.0mm thick**
- **Shutter Guide: G-65 GI Guide Rails**
- **Operated by: Motor with one unit push button switch & manual override**

Fire Rated Rolling Shutter

Sr .No.	Specification	Fire Rated Rolling Shutter - SKB BS 476
1	**Shutter Curtain**	SKB-A7 -Zinc Coated Solid Slats Powder Coated to RAL colour manufacturer std
2	**Guide Rail**	G-65 GI Guide Rails
3	**Bottom Bar**	Powder coated SKB-T-120
4	**Type of Mounting**	Standard
5	**Motor Drive Unit**	Power Source: **230v 50Hz 1 phase for Size 2500 W x 2350 H- mm** **And 440v 50Hz 3 Phase for Size 6150 (W) x 9150 (H)** Manual Chain Override One unit push button switch Gravity drop level Auto close by relay switch after receive of 24vdc fire signal
6	**Standard RAL colors:**	RAL 9010 (White) / RAL 7025 (Gray)
7	**Protection Category**	BS 476

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Scope
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Price Pune

Delivery : 9-10 weeks for Fire rated shutters from the date of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% advance along with purchase order & balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of Installation.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333.**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd