NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Tata Steel Limited
Narendra Pur P.O Shibapur
Meramandali, Odisha 759121,INDIA

Date : 28.03.2022
RFQ No : 0199904824/1500115194/A01
Quote NO : **MHE_21.22.0055R**
Kind Attn : Mr. KUNAL KASHYAP

Project Name & Location: Tata Steel Limited, Odisha

Subject : Quotation for MANUAL MOBILE DOCK RAMP

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**MANUAL MOBILE DOCK RAMP** DYNAMIC CAPACITY=10000 KG STATIC CAPACITY=12000 KG SIZE WXL=2000X11500 MM LIP EXTENSION=350 MM WORK RNG ABV/BLW=1200/1600 MM OPERATION: MANUAL	**2**	**7,65,000**	**15,30,000**	**25,000**	**50,000**
	Total Amount Excluding Taxes			**15,30,000**		**50,000**
2	GST Extra @ 18%	18%				**Extra At Actual**
3	P&F Charges	3%				**Extra At Actual**
4	Transportation Charges (40ft container)					**Extra At Actual**
5	Insurance Charges					**Extra At Actual**
6	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

MANUAL MOBILE DOCK RAMP

Sr. No.	Parameters	Specification
1	DYNAMIC CAPACITY	10000 KG
2	STATIC CAPACITY	12000 KG
3	SIZE WXL	2000 MM X 11500 MM
4	LIP EXTENSION	350 MM
5	WORK RNG ABV/BLW	1200/1600 MM
6	CORROSION RESISTANCE	PAINTED
7	OPERATION	MANUAL

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-10 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 100% payment against submission of Invoice within 30 days.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 85510 93333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd