NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1606 **Date : 08.05.2019**

Lupin Ltd
159, C.S.T Road
Kalina, Santacruz
Mumbai - 400098

Kind Attn : Mr. Umesh Pawar
Email ID : umeshpawar@lupin.com
Contact No : 9930973133

Project Name And Location : Lupin Goa

Subject : Quotation for Five Leaf Motorized Telescopic Sliding Gate & Compund Wall Frame

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Five Leaf Telescopic Motorised Sliding Gate (One Leaf will be fixed and Four Leafs will be Movable) (Supply + Installation)**				
	Telescopic Sliding Gate - (W)7.52 mtr x (H)2.2 mtr **• For Post- 75x75x3.2 mm MS Tube** **• Outer tube- 75x75x3.2mm MS Tube** **• Innear tube - 75x25x 2mm MS Tube** **• Gap Between tubes - 125 mm**				
1	Size (w) 7520 mm x (h) 2200 mm	1	No	965,000	965,000
B	**Five Leaf Telescopic Motorised Sliding Gate (One Leaf will be fixed and Four Leafs will be Movable) (Supply + Installation)**				
	Telescopic Sliding Gate - (W)7.2 mtr x (H)2.2 mtr **• For Post- 75x75x3.2 mm MS Tube** **• Outer tube- 75x75x3.2mm MS Tube** **• Innear tube - 75x25x 2mm MS Tube** **• Gap Between tubes - 125 mm**				
1	Size (w) 7200 mm x (h) 2200 mm	1	No	955,000	955,000
C	**Compund Wall Frame**				
1	2650W X 1600H	1	No	75,000	**75,000**
2	2930W X 1600H	1	No	80,000	**80,000**
3	4350W X 1600H	1	No	100,000	**100,000**
4	9025W X 1600H	1	No	150,000	**150,000**
5	4800W X 1600H	1	No	110,000	**110,000**
GST Pune	**27AAECN0437H1ZM**			**Grand Total**	**2,435,000**

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material.
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2
In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST Extra 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

With Best Regards
Varsha
8551091333
For Nihva Technologies Pvt Ltd