Radisson Blu

Work Order

Dated: 12.07.2024
RBG/CDPL/24-25/**0121**

M/S NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom,
Thermax chowk, MIDC, Chinchwad.
Pune – 411019.
GST No-

Contact Person Mr. Vijay, Ph. No-8551093333.

Dear Sir,
It is with reference to your quotation for **Automatic Retractable Roofing work with materials at Radisson Blu Mohaddipur Gorakhpur (UP).** We are pleased to confirmed the order for the same as per under mentioned terms & conditions.

Sr. No.	Description	Size (Mtr.)	Qty in Nos	Supply & Installation Charges in INR
1	Automatic Retractable Roof.	• 5.1m(W) X 31.8m(L) • 10 Panels • Centre Opening	2	1,20,00,000
2	Automatic Retractable Roof.	• 5.5m (W) X 29.1m(L) • 10 Panels. • Centre Opening	1	
		Total without Taxes		**1,20,00,000**
		GST Extra @ 18%		2160000
		G. TOTAL AMOUNT		**1,41,60,000**
		P&F Charges @ 3%		inclusive
		Transportation Charges		Extra at actual at client account
		Unloading Charges @ Site		at client account
		LED Lighting		Inclusive

Amount in word: - One crore Forty-one lakh and sixty thousand rupees only.

NIHVA TECH. PVT. LTD. PUNE

22/7/24

Radisson Blu

Technical Specification

01. Polycarbonate Compact Clear/Embossed. (4mm)
02. Profile: Powder Coated Aluminium Frame. (60 mic)
03. Guide: AL/MS/SS Guide.
04. Motor Mechanism with control panel.
    a. Push button/Remote Controlled.
    b. Single Phase Bi-directional Motor. (Make-Nice with one year's warranty)
    c. Power- As per Roof Dimension.
    d. Mechanical Limit Switch.
    e. Rack and Pinion Arrangement. (Sliders Roller Mechanism)
05. EPDM Gaskets and sealants.
06. SS Fasteners.

General Conditions

01. Continuous uninterrupted access to installation section or as agreed separately.
02. Provision of 230 V power supply for hand tools
03. A dry and secure area, not in direct sunlight is to be provided for storage of product component
04. Access to site between 7 am to 8 pm should be provided
05. Any storage costs for material due to delay outside of NIHVA, will be in client scope.
06. The project time indicated does not consider adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly.
07. Installation will start after receiving of Site Readiness Photographs or written Email communication.
08. We will mobilize the Installation Team in 3 - 4 working days, after receipt of Site Readiness Confirmation.
09. For any reason if we need to stop our installation and demobilize the team without completing the work, then extra cost will be applicable for Remobilizing the Team.
10. If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.

Please find below List which are in Hotel Scope

01. Secured and fully covered Store area to keep the material
02. Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site.
03. Electrical Supply on the site single phase/three phase points at different places.
04. Any civil / masonry/structural work required.
05. All structure support required.
06. In Case of any changes in the layout as per site requirements after the shipment of material, the additional quantities and wastage.
07. Conduits, Cables required

NIHVA TECHNOLOGIES Pvt. Ltd.

22/7/24

Radisson Blu

Terms & Conditions

1 Payment: 40% advance against security cheque, 25% against delivery of material at site, and 15% after start work at site and 20% after completion of work.
2 Your labour will be insured at your cost. If any mishap occurs during work the hotel will Not be responsible for it and you shall keep the hotel indemnified against any such eventuality.
3. All statutory labour compliances are in your scope and you shall keep the hotel indemnified against it.
4 Freight: Extra and applicable.
5 Taxes Extra as applicable.
6 You have to follow all instructions as per our Chief Engineers.
7 All Material, labour, machinery & Repair will be in vendor scope.
8 After 2-year warranty, non-comprehensive AMC will be provided by NIHVA at an additional cost
9 All disputes are subject to Gorakhpur Jurisdiction.
10 Work to be start from one receive the advance payment
11 Safety: As per industry norms the vendor will keep Radisson Hotel. Indemnified against any accident injury to the vendor works as well as to the third party.
12. Accomodations at dormitory will be provided by hotel.
13. General Terms & conditions

1. The contractor will ensure that his workmen strictly follow the safety procedures and is responsible for general maintenance/housekeeping requirements of his materials/debris arising out of his own installation works or rectification works, if any will be disposed off at his own expenses. If any lapse on account of non performance, the company shall get the work done without any notice through either departmental labour or any other contractor and recover the cost from the contractor's bill, irrespective of whether the contractor's acknowledgement is received or not.
2. The Contractor will strictly abide by the schedule given to him to keep up the progress of work at site, which will be reviewed as frequently as required.
3. The Contractor shall co-ordinate with all other contractors/ agencies engaged by the employer.
4. The contractor will indemnify the Employer in case of any accident, injury, or death of any workman employed by the contractor for the execution of the work. The contractor shall be liable for payment of compensation arising out of the same.
5. Income Tax shall be deducted at source as per the statutory regulation of the Government.
6. In the event of any of the services rendered by you are found to be unsatisfactory, or due to Administrative reasons we reserves right to terminate this contract with intimation at any stage during the tenure of contract. However, in the event of such premature termination of the contract, we will pay all dues and payments for the bonafied and certified work carried out as per work order, till the date of such termination.
7. WC Policy is to be taken by vendor.

The Contractor shall employ qualified technicians, and labours in sufficient numbers and of proper caliber directly to maintain the required rate of progress and to ensure workmanship to the degree specified in the contract and to the satisfaction of the employer/Engineer in charge. The contractor shall not employ any person who has not completed his eighteen years of age and shall indemnify the employer regarding any penalty/compensation arising out of non-adherence to statutory regulations/ provisions of any Labour Laws including ESI, P.F., and Workmen Compensation Act.

NIHVA TECHNOLOGIES PVT. LTD. PUNE

22/7/24

Radisson Blu

Any minor material or service which is required to be deployed for the job, beyond the one mentioned in the scope shall be considered incidental to the works and no additional payments shall be made.

ARBITRATION.
In case of any dispute, if the same is not resolved by mutual discussions, it will be referred to the sole arbitrator appointed by the Ordering Party. The arbitration proceedings shall be conducted at Gorakhpur in accordance with the provisions of Arbitration & Conciliation Act, 1996.
JURISDICTION

Yours Sincerely.

Purchase Manager
Authorised Signatory
Radisson Blue Hotel

Chief Engineer
Authorised Signatory
Radisson Blue Hotel

Content have been read,
Understood and accepted
Authorised signatory
M/S NIHVA Technologies Pvt Ltd

Authorized Signatory.

General Manager
Radisson Blu
Gorakhpur (UP)

NIHVA TECHNOLOGIES PVT. LTD. PUNE
22/7/24