Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.1440 **Date: 04/08/2019**

Oji India Packaging Pvt.Ltd.

Plot No. H-14, Sipcot industrial Park, Vallam Vadagal
Sriperumbudur, Chennai - 602105
Tamil Nadu -India

Kind Attention: Mr. Rajiv Sherawat

Phone:- (982) 852-2532
Email ID: rajiv.kumar@ojpack.com

Project Name And Location :

Subject : Quote for - Nihva make Dock Leveller

Dear Sir,

Thank you for your opportunity and trust shown on “NIHVA.” your preferred partner for innovative solutions.This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer :-

Sl.No.	Description	Price	Qty	Unit	Total
1.	NIHVA Dock Leveller Platform Size : (W) 2200 mm x (L) 3000 mm -Capcity : 6 Ton -Dock Operation mode : AC Power Pack Hydraulically Operated - Lip Size : (W) 2200 mm x (L) 400 mm -Dock Leveller Shut Height : 550 mm -Working Length : 3400 mm -Deck Plate (MS Chequered) 8 mm Thick - Lip Plate : 16 mm Thick No.of Deck Cylinder : 2 Lip Cylinder : 1 Pair of Dock Bumper - 1 (Supply + Installation)	₹ 220,000.00	1	Nos	₹ 220,000.00

Sub Total	₹ 220,000.00
Grand Total	**₹ 220,000.00**

GST Pune	27AAECN0437H1ZM

Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.1440 **Date: 04/08/2019**

General Pre requisite at site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required
5 Scaffolding require for Installation it is in client scope

Limit of Supply

1 Provide place to store the material to be installed
2 Be responsible for the safe custody of all material
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel

Client Scope

1 Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Existing/Repair/ Modification/ Refurbishment charges will be extra

Terms & Conditions

1 **Price** : Ex works Pune
2 **P & F Charges**: @3% of Total Supply Value
3 **Freight Notes**: Extra as applicable
4 **Payment**: 80% Advance along with confirm purchase order & Balance 20% before dispatch
5 **Taxes**: GST @ 18%
6 **Validity**: Validity of Offer is 15 days from the date of quotation.
7 **Warranty**: 12 months from the date of supply
8 **Delivery** : 5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
9 **Insurance :**Extra As applicable

Please feel free to Contact **Mr. Arjun Patil on (855) 109-6333** for any further Clarification /Information in this Concern.

With Best Regards

Smita Khare
+91-9637991333
For Nihva Technologies Pvt Ltd