NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Insmart System
5-234/1/1, H.P. Road, Moosapet, Hyderabad - 500018, Telangana, India.

Date : 04.01.2020
Quote NO : SQT.19.20.2172R1
Kind Attn : Mr. Bhaskar
Email Id : bhaskar.khatravath@insmartsystems.co.in
Contact No: **9121177178**

Project Name & Location: Bowl feeder ; Hyderabad Telengana

Subject : Quotation for Bowl feeder

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Bowl Feeder	5	1,25,000	6,25,000	NA	
	Total			**6,25,000**		
2	P&F Charges	3%		**18,750**		
	Total Without Taxes			**6,43,750**		
	GST Extra @ 18%	18%		1,15,875		
	Total With Taxes			**7,59,625**		
3	Transportation Charges			**In Client Scope**		
4	Unloading Charges @ Site			**In Client Scope**		

B) Technical Specification

Parameters	Specification
Material	S.S.202
Outlet	Single
Coil	4 Nos /1 Nos
Vibration control	Adjusting knob provision
Feed rate	30 piece/minute
Bowl feeder height	1300 mm(from Ground)
Discharge height	1300 mm(from Ground)
Hopper capacity	5kg

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 8- 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil- 8551096333**

With Best Regards
Yogita
8530872333
For NIHVA Technologies Pvt Ltd