NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Vacmet India Ltd
Unit-V, Plot no.1, MPAKVN New Industrial Area,
Ujjaini 454773 (M.P.) India

Date : 05.02.2021
Quote NO : SQT.20.21.2999
Kind Attn : Mr Umesh jain
Email Id : umeshjain@vpiplmail.co.in
Contact No: 7089907901

Subject : Quotation for GI Motorised Rolling Shutter , GI Gear operated Rolling Shutter & NIHVA Make Rapid Roll Up Door .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Make Rapid Roll-Up Door**	1000	1000	4	256,000	1,024,000	15,000	60,000
2	**NIHVA Make Rapid Roll-Up Door**	2000	2000	4	287,000	1,148,000	15,000	60,000
3	**NIHVA Make Rapid Roll-Up Door**	3500	4000	8	331,000	2,648,000	15,000	120,000
4	**GI Motorised Rolling Shutter**	3500	4000	12	106,000	1,272,000	15,000	180,000
5	**GI Motorised Rolling Shutter**	2500	2500	7	69,000	483,000	15,000	105,000
6	**GI Motorised Rolling Shutter**	3000	3000	6	80,000	480,000	15,000	90,000
7	**GI Gear Operated Rolling Shutter**	5000	5000	3	120,000	360,000	15,000	45,000
8	**GI Gear Operated Rolling Shutter**	3500	4000	4	75,000	300,000	15,000	60,000
			Total			**7,715,000**		**720,000**
			P&F Charges	3%		**231,450**		
			Total Without Taxes			**7,946,450**		**720,000**
			GST Extra @ 18%	18%		1,430,361		129,600
			Total With Taxes			**9,376,811**		**849,600**
	Transportation Charges					**Extra at actual**		
	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Make Rapid Roll-Up Door

- **Safe & for continous operations**
- **Self Supporting Construction with anti crash protection system for bottom profile**
- **Smooth & silent opening & closing**
- **Can be equipped with full vision PVC curtain**
- **Modular Interchaegable panels permit to replace worn & damged panels**



Sr. No	Specification	NIHVA Make Rapid Roll-Up Door
1	**Description**	Flexiable High Performance Door , Opening in vertical direction for interior use in wind protected area
2	**Side Frames**	Made of Aluminium
3	**Door Curtain**	Made of transparent PVC with Fabric reinforcement stripes ultramarine(similar to RAL 5002) or red (similar to RAL 3002).
4	**Top Roll**	Made of Anodized Aluminium
5	**Opening / Closing Speed**	1-0 m/s closing speed 0.8m/s
6	**Wind load resistance**	class 1 (EN 12424)
7	**Control Panel**	4 Push Button operated
8	**Drive unit:**	Hollow shaft gear motor.
9	**Bottom profile**	anodized aluminium.
10	**Plastic control cabinet**	IP 65
11	**Safety:**	Electrical safety contact edge
		Evaluation via integrated cable chain
		Door line photocell in the side frames
		push button Open-Emergency Stop-Close with integral automatic timer
		Drop down protection by integrated balancing system

GI Motorised Rolling Shutter





Sr .No.	Specification	GI Motorized Rolling Shutter
1	Description:	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1 mm thick .
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 140 mm x 2.5 mm thick
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm
12	Surface finish	Powder coated
13	Drive Unit & Mounting Type	Indirect Drive, Electric Motor - Direct Mounting - Sprocket chain arrangement
14	3 Station Push Button	Included

GI Gear Operated Rolling Shutter

Sr .No.	Specification	GI Gear Operated Rolling Shutter
1	Description:	Gear Operated Rolling Shutter with GI Slats with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1 mm thick GI.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm GF mm
12	Surface finish	Powder coated
13	Operations	Gear Assembly .

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 12-13 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 08551092333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd