NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

VDL Pinnacle Engineering India Pvt. Ltd.
MIDC Bhosari, Pune 411026

Date : 02.02.2021
Quote NO : SQT.20.21.2885
Kind Attn : Mr.Vishwas Gangakhedkar
Email Id : V.Gangakhedkar@vdlpinnacle.com
Contact No: 9307305183

Subject : Quotation for Machine Protection Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Albany Make Machine Protection High Speed Door - RP 300**	3600	1500	2	734,182	1,468,364	20,000	40,000
2	**Albany Make Machine Protection High Speed Door - RP 300**	4000	1500	2	742,210	1,484,420	20,000	40,000
3	**Albany Make Machine Protection High Speed Door - RP 300**	1800	1500	2	684,200	1,368,400	20,000	40,000
			Total			**4,321,184**		**120,000**
4	P&F Charges			3%		**129,636**		
	Total Without Taxes					**4,450,820**		**120,000**
	GST Extra @ 18%			18%		801,148		21,600
	Total With Taxes					**5,251,967**		**141,600**
5	Transportation Charges					**Extra at actual**		
6	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Albany make Machine Protection Door RP300

Sr .No.	Specification	Albany make Machine Protection Door RP300
1	**Door version:**	Vertical Rapid Roller Door for machine protection.
2	**Side Frames:**	Aluminum anodized two parts, to have easy access to switches and service.
3	**Door blade:**	Rolltex Curtain
4	**Bottom beam**	Aluminium anodized.
5	**Drive unit:**	Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)
6	**Opening / closing speed:**	Approx. max. 2,0 / 1,2 m/s
7	**Control system:**	MCC Vector Control
8	**Power suppy:**	3/(N)/PE 230/380/400/415 V, 50 Hz
9	**Safety features:**	Safety edge with cable chain integrated in side frames, pre running photocell.
10	**Safety limit switch:**	1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10-12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551082333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd