1 ITEMS TO BE QUOTED

The following items (material and services), required for Hindustan Petroleum Corporation Limited (HPCL), Vishakhapatnam (Visakh Refinery), Andhra Pradesh, India shall be supplied in accordance with the requirement specified in this requisition and documents attached herewith.

Sl. No.	Description	Requirement	Scope of supply & work	Remarks
1	Capacity	6 Ton	By Supplier	Forklift self-weight + Big Bag weight + Operator weight + Pallet weight + 20% margin = 6 Ton
2	Height Adjustment	Above Dock Operation : 600 mm (Minimum), Below Dock Operation: 300 mm (Minimum).	By Supplier	-
3	Quantity of dock leveller	Two (2)	By Supplier	-
4	Platform Size	To be informed by supplier (Refer attachment-1)	By Supplier	-
5	Hydraulic system	Complete hydraulic system including all accessories and fittings [Deck assembly, Frame assembly, Lip assembly, hydraulic cylinder assembly for Deck, hydraulic cylinder assembly for Lip, Hydraulic power pack assembly (electric motor driven), complete hose assembly, safety skirt assembly, control panel, safety appurtenances & guards, rubber buffers etc.]	By Supplier	-

ALL RIGHTS RESERVED

THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF L&T HYDROCARBON ENGINEERING (LTHE) AND THE COPYRIGHT THEREIN IS VESTED IN LTHE NO PART OF THIS DOCUMENT, DATA, OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF LTHE.

Sl. No.	Description	Requirement	Scope of supply & work	Remarks
6	Electrical equipment including motor (including Main & Auxiliary Terminal Boxes)	Hazardous Area Classification for electrical equipment : 1.Safe Area (Base Quote) 2.Zone 22, IIIC, T4 (Optional Quote) All the electrical equipment, design and testing shall be as per the project specification / Data sheet / documents enclosed with the requisition. As per MR and its attachment for Zone 1 and 2, Motor selection criteria is as follow: (X)For Zone-2 Motors, For < 100 KW, Ex-e motors shall be used, except for following cases: 1) Ex-de motors shall be used in zone-2 areas having frequent start-stop requirement. 2) In case where there is manufacturing limitation for Ex'e' Motor, Ex'de' motor is also acceptable. Ex'e motors shall be selected without the requirement of prestart purging. However for the zone 22, vendor to select the motor complying all relevant codes and standards Motor starter shall be supplier's scope. FRP Canopy for motor protection shall be provided by supplier	By Supplier	Supplier to design all the electrical equipment as per the MR attachments.

ALL RIGHTS RESERVED

THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF L&T HYDROCARBON ENGINEERING (LTHE) AND THE COPYRIGHT THEREIN IS VESTED IN LTHE NO PART OF THIS DOCUMENT, DATA, OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF LTHE.

Sl. No.	Description	Requirement	Scope of supply & work	Remarks
		For Motor. Shock Pulse Measurement provision shall be provided at NDE end and along with soft feet test at supplier shop. DRAWINGS AND DOCUMENTS requirement which Vendor needs to submit in post order shall be discuss during Kick of Meeting.		
7	Local Panel / Distribution panel/Field MCC Local Control Station for Dock leveler	LTHE will provide only single point power supply (Power feeder: 415 V ± 10% / 50 Hz ± 3%) to Distribution panel/Field MCC of Dock Leveler, Further distribution including Distribution panel/Field MCC, Cables (power, electrical control, earth and special cable (if required), Lugs, Local control station, cable tray, conduit, Hardware, Glands and all other equipment to complete the package shall be in Supplier's scope along with engineering. Any Local control station/ Start stop push button required shall be in Supplier's scope only.	By Supplier	Supplier to design all the electrical equipment / items as per the MR attachments.
8	Spares	1. Vendor to provide Mandatory Spares as per B016-504-16-50-SL-9509. 2. Spare parts for Erection, Pre commissioning and Start-up based on Supplier's recommendation 3. Spare parts for 2 years normal operation as per Supplier's recommendation	By Supplier	-

ALL RIGHTS RESERVED

THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF L&T HYDROCARBON ENGINEERING (LTHE) AND THE COPYRIGHT THEREIN IS VESTED IN LTHE NO PART OF THIS DOCUMENT, DATA, OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF LTHE.

Sl. No.	Description	Requirement	Scope of supply & work	Remarks
		4. SPECIAL TOOLS & TACKLES as per Supplier's recommendation.		
9	Earthing Requirement	LTHE shall provide earthing connection at single point only and further connection to package equipment and within the skid / battery limit shall be in scope of supplier. Earthing bar required for this package shall be in scope of supplier.	By Supplier	Supplier to design all the electrical equipment / items as per the MR attachments.
10	Field Instruments & controls	Minimum IP protection for instrumentation items shall be Weatherproof to IP-65. All Instruments items shall be suitable to Hazardous area Zone 1, IIC, T4 & all instrumentation items shall be CCOE/PESO certified. Industrial grade instrumentation items shall be offered.	By Supplier	-
11	Necessary structural support & bolts	Angle bar around the dock leveler and Anchor bolts	By Supplier	1. Structural steel shall be as per EIL design basis for Civil and Structural. 2. Anchor bolts shall be as per EIL standard drawing.
12	Input for civil work	Mounting detail of anchor bolts and Foundation load details	By Supplier	-
13	Emergency locking / protection system	Immobilizer security system in the event of emergency stop or power failure. Any braking system if required shall be considered by supplier in their scope of supply / work	By Supplier	-
14	Bumpers	As per Supplier Recommendation, If required	By Supplier	-

ALL RIGHTS RESERVED

THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF L&T HYDROCARBON ENGINEERING (LTHE) AND THE COPYRIGHT THEREIN IS VESTED IN LTHE NO PART OF THIS DOCUMENT, DATA, OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF LTHE.

Sl. No.	Description	Requirement	Scope of supply & work	Remarks
15	Personnel safeguard	Side mobile toe guards, Visual signs on mobile parts etc.	By Supplier	-
16	Any other accessories	Any other accessories, equipment which are required but not listed in this specification shall be considered by supplier in their scope	By supplier	-
17	First Fill of hydraulic oil	Supplier shall consider first fill of all lubricants / hydraulic oils and replenishment of any loss of these during commissioning & PG testing and for operation & maintenance of Six (6) months after commissioning in their scope of supply.	By Supplier	-
18	Noise level	Noise limit shall be 85 dBA at 1 m distance from the source.	By supplier	-
19	Spare parts	Spares required for 2-Years normal operation & maintenance (separate quotation) Spares required for construction / commissioning.	By supplier	(As per supplier recommendation)
20	Approved Motor Vendors	Sub Supplier shall be as per attached supplier list. (Refer Mechanical attachment – 2)	By supplier	-

Sub-Systems / Auxiliary items/ Instruments not listed in this requisition / Annexure / attachment but required to meet the functional requirements specified in the documents shall be provided by supplier.

ALL RIGHTS RESERVED

THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF L&T HYDROCARBON ENGINEERING (LTHE) AND THE COPYRIGHT THEREIN IS VESTED IN LTHE NO PART OF THIS DOCUMENT, DATA, OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF LTHE.