NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Dandekar & Associates
Pune

Date : 12.02.2021
Quote NO : SQT.20-21.3013R
Kind Attn : Mr. Vikram
Email Id : dandekar.associates@gmail.com
Contact No: 9665157700

Subject : Quotation for Motorised Full Height Trunstile

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
Option-1	**NIHVA-Double Lane Motorised Full Height Turnstile Gate: SS 304** • It has zero position of self -checking, easy for users to maintain and use. • There is alarm notice funtion when illegal access. • Avoid bump funtion: When the turnstile does not receive the open signals, the baffle will lock automatically. • IR/mechanical dual anti-lined funtion: When the baffle has problem in reseng, it will stop working automatically in certain time, and the potency is small, will make an alarm sound at the same time. • Reseng automatically: the passenger read effectively, the system will cancel this access authority if they will not access in certain time. • Standard wiring connection: can connect with many kinds of card readers, and can remote control through the computer. • The whole system works steadily, and the noise is very low. • Fastner and hardware for Fitting of Full height turnstile. • Unlock time: 0.2s • Pass rate: 20 person/min each from both gates; •Input:100V~240V; Driving Voltage: 24v; • Weight:400 Kg	10	4,59,500	45,95,000	20,000	2,00,000
Option-2	**NIHVA-Single Lane Full Height Turnstile Gate: SS 304** • It has zero position of self -checking, easy for users to maintain and use. • There is alarm notice funtion when illegal access. • Avoid bump funtion: When the turnstile does not receive the open signals, the baffle will lock automatically. • IR/mechanical dual anti-lined funtion: When the baffle has problem in reseng, it will stop working automatically in certain time, and the potency is small, will make an alarm sound at the same time. • Reseng automatically: the passenger read effectively, the system will cancel this access authority if they will not access in certain time. • Standard wiring connection: can connect with many kinds of card readers, and can remote control through the computer. • The whole system works steadily, and the noise is very low. • Fastner and hardware for Fitting of Full height turnstile. • Unlock time: 0.2s • Pass rate: 30 person/min each from both gates; Pass Width: 500-700mm; • Input: 100V~240V; Driving Voltage: 24v; Environment: -20~60°c; • Power Consumption: 35w • Weight:220kg	10	2,97,500	29,75,000	20,000	2,00,000
	Optional					
1	**Smart card reader**	1	4,850	At Actual		
2	**Finger print attendance system + card reader**	1	23,500	At Actual		
3	**Controller for entrance system with SMPS power supply**	1	19,500	At Actual		
	P&F Charges @ 3%	3%				Extra At Actual
	GST Extra @ 18%	18%				Extra At Actual
4	Transportation Charges					Included
5	Unloading Charges @ Site					Included

B) **Technical Specification**

Motorised Full Height Trunstile

Sr .No.	Description	Specifications
1	Framework	304 SS
2	Finishing	Brushed
3	Dimension	(L) 2150 mm x (W) 1500 mm x (H) 2220 mm
4	Pass Width	500 - 700 mm
5	Pass Rate	20 persons/min
6	Operation	Single/Bi-directional
7	Rotor Type	4 arm x 90°
8	Mechanism	Electro-Mechanical
9	Locking	25° from previous rest position
10	Power Voltage	AC 220V +/- 10% 50-60Hz
11	Power Consumption	80W per lane
12	Mode	Fail Safe
13	Operating Temprature	-20°C - 55°C
14	Integration	Any Access control system

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd