**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**TRANS ENGINEERS INDIA PVT LTD**
Gat No. 1552A & 1326A, Dehu-Alandi Road,
Shelar Vasti, Chikhali, Pune-411062

**Date :** 11.1.2021
**Quote NO :** SQT.20.21.2924R2
**Kind Attn :** Chaitanya Kuila
**Email Id :** chaitanyakuila@transengineers.com
**Contact No:** 8956709129

**Project, Location : Pune**

**Subject : Revised Quotation for Gear Operated Single Skin Rolling Shutter**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 2 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **GI Single Skin Gear Operated Rolling Shutter** | 3000 | 2980 | 2 | 55,000 | 110,000 | Inclusive | |
| | **Total** | | | **2** | | **110,000** | | |
| 2 | P&F Charges | | | 0% | | - | | |
| | **Total Without Taxes** | | | | | 110,000 | | - |
| | GST Extra @ 18% | | | 18% | | 19,800.00 | | - |
| | **Total With Taxes** | | | | | **129,800** | | **-** |
| 3 | Transportation Charges | | | | | Inclusive | | |
| 4 | Unloading Charges @ Site | | | | | In Client Scope | | |

**Note :** **Price Rs 55000/-, Subject to Submission of 10% PBG**

**Price Rs 54000/-, No PBG**

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Gear Operated Rolling Shutter**

| Sr .No. | Specification | GI Gear Operated Rolling Shutter |
|---|---|---|
| 1 | **Description** | Gear Operated Rolling Shutter with GI slats with thickness of 1 mm. |
| 2 | **Mounting Location area** | Inside area |
| 3 | **Mounting Surface** | Side Brackets: On Concrete |
| 4 | **Curtain Panel** | The panel made of 1.0mm thick GI. |
| 5 | **Curtain panel size** | 75mm wide |
| 6 | **Curtain Profile** | Curved |
| 7 | **Bottom Profile** | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 8 | **Side Guide Profile** | M.S." U" Shaped profile |
| 9 | **Roller Shaft** | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h |
| 10 | **Hood Cover** | Made of GI Sheet Thickness 0.9 mm GF mm |
| 11 | **Surface finish** | 2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer |
| 12 | **Operation** | Gear Assembly (Manual Handle) |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description |
|---|---|
| 1 | Secured and fully covered Store area to keep the material |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site |
| 3 | Electrical Supply on the site single phase/three phase points at different places. |
| 4 | Any civil / masonry/structural work required |
| 5 | All structure support required |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. |
| 7 | Conduits, Cables required |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 12 Days from the date of receipt of confirmed Purchase Order & Drawing Approval.

**Payment** : 90% after delivery and before Installation, 10% after installation (with PBG for 12 Months)

**Validity** : Validity of Offer is 3 days from the date of quotation (As Steel Prices are increasing day by day).

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Amol Gaware on 7758820333** For any further Clarification /Information in this Concern.

**With Best Regards**
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd