Quote no	VTEC ENG 01-01-190121
Date	19-01-2021

TECHNO - COMMERCIAL PROPOSAL

Client Name	VTEC ENG	GST No	
Address			
Address			
Contact Person 1	Mr/Ms		
Contact Person 2	Mr/Ms		
Telephone 1	+91		
Telephone 2	+91		
email 1	vtec.engineers@gmail.com		
email 2			
PAN NO			

Code	Product description	Clear opening Dimensions(W x L)	Qty	Per unit Supply Value	Total Supply Value
DL	**ZK Barcelona Dock leveller**	**(2000W) mm X (2500L) mm**	***20***	1,72,957 INR	34,59,145 INR
	Sub Total Supply				**34,59,145 INR**
	Sub Total Installation				**1,16,200 INR**

Technical Specifications

Platform : made from sheet metal (6 to 8 mm thick) with profile lower slip reinforced with steel profiles
Chassis : Self-supporting-Z. **Lip**: Steel plate with anti-slip profile.
Hydraulic system : Two independent hydraulic cylinders operate the platform and the lip. **Color RAL 9005**.
Dynamic capacity 60 kN. Chassis height **600** and lip Length **400**.
Security : Hydraulic emergency, total stop in case of power outage, reset after power outage, **Anti entrapment security** and lateral safety markings yellow / black.
Rubber bumpers optional.

1	Bumpers	YES
2	Tapered Lip (45º lip cut)	YES

Comments:

Code	Product description	Clear opening Dimensions(W x H)	Qty	Per unit Supply Value	Total Supply Value
ISEC	**ZK Bilbao Jumbo sectional door**	**(3000W) mm X (4000H) mm**	***20***	2,07,318 INR	41,46,368 INR
	Sub Total Supply				**41,46,368 INR**
	Sub Total Installation				**1,75,000 INR**

Technical Specifications

Panel : Individual sections are composed of doublewall steel strips (500 or 625 mm in height, height compensation upper section), with a leaf thickness of 45 mm and **CFC-free PUR foam core**.
Guides : vertical rail with galvanized steel sheet angle with **hand-protection**. The door's horizontal positioning is carried out in an extremely stable rail. The individual sections are joined with intermediate hinges and hinge-sections fitted with adjustable, **ball-mounted plastic pins**.
Lintel : standard (height door + 450 mm). Under CE marking regulation. Other lintel O**ptional lintel** : vertical lift. Including all safety features.
One window included, **manual opening by chain system**. **Automatic** opening available as option.

1	Lintel	Standard
2	Automation	YES
3	Wall Type	Panel

Comments:

Code	Product description	Clear opening Dimensions(W x H)	Qty	Per unit Supply Value	Total Supply Value
HRS	**ZK Madrid High speed roll up door**	**(3000W) mm X (3000H) mm**	***20***	1,88,263 INR	37,65,256 INR
	Sub Total Supply				**37,65,256 INR**
	Sub Total Installation				**1,16,200 INR**

Technical Specifications

Application : Inside the building, Class 2 for wind (450 Pa).
Guides, Lintel and Cover Lintel : **Anodized extruded aluminium** (20 µ, T5 treatment) with cable housing (hidden cables). Stainless steel roller and console.
PVC Canvas : 2-4(depending size) reinforced bars, 1 mm. thickness, 950 gr/m2, fireproof M2, conform to norm UNE-EN 1421.
Profiles and screws in **stainless steel**. Safety Light Curtain 2000H or 2500H.
height (doors above 2600H), not necessary safety edge.
Drive : High quality Motor and IP65 Control box very easy to programm.
Opening speed 0.93 m/s. **Door preinstalled**.
Under CE marking regulation **UNE-EN-13241-1:2004**.
Opening options : Push buttom both sides as standard, multiple opening options available.

1	color	Blue
2	Transperent	NO
3	Pull cord	NO
4	Laser	NO
5	Remote	NO
6	Radar	NO
7	Beacon Light	NO
8	Motor Side	Left

Comments:

Code	Product description	Clear opening Dimensions(W x H)	Qty	Per unit Supply Value	Total Supply Value
FF	**ZK Bilbao Flip flap door**	**(2200W) mm X (2000H) mm**	***1***	74,181 INR	74,181 INR
	Sub Total Supply				**74,181 INR**
	Sub Total Installation				**5,880 INR**

Technical Specifications

Leaf : 40 mm thickness individually injected in Polyisocyanurate (**PIR Insulation**) (40-45 kg/m3), 6mm polyethylene (PE) leaf with co-extruded **EPDM gaskets**.
Included methacrylate **Porthole** 400H*280L and extra polyethylene Protection in the base 300 mm heigh.
Frame: L-shaped extruded pre coated **aluminium** with counter frame adapted to all wall panel thicknesses.
Hinges : Specially designed **stainless steel hinges** for intensive use.
optional polyamide. optional PCGI leaf finished.

1	Finish	PE
2	Bumpers	YES
3	Number of Leaves	2
4	Lock with Key	NO
5	Wall Type	Panel
6	Wall Panel Thickness	80

Comments:

Code	Product description	Clear opening Dimensions(W x H)	Qty	Per unit Supply Value	Total Supply Value
FF	**ZK Bilbao Flip flap door**	**(2200W) mm X (2200H) mm**	***3***	76,806 INR	2,30,419 INR
	Sub Total Supply				**2,30,419 INR**
	Sub Total Installation				**17,640 INR**

Technical Specifications

Leaf : 40 mm thickness individually injected in Polyisocyanurate (**PIR Insulation**) (40-45 kg/m3), 6mm polyethylene (PE) leaf with co-extruded **EPDM gaskets**.
Included methacrylate **Porthole** 400H*280L and extra polyethylene Protection in the base 300 mm heigh.
Frame: L-shaped extruded pre coated **aluminium** with counter frame adapted to all wall panel thicknesses.
Hinges : Specially designed **stainless steel hinges** for intensive use.
optional polyamide. optional PCGI leaf finished.

1	Finish	PE
2	Bumpers	YES
3	Number of Leaves	2
4	Lock with Key	NO
5	Wall Type	Panel
6	Wall Panel Thickness	80

Comments:

Total No of Units	**64**
Total Supply value	**1,16,75,369 INR**
Total Installation value	**4,30,920 INR**
GST18	**21,79,132 INR**
Total (Exclusive Taxes)	**1,21,06,289 INR**

NOTES:

ORDER ACCEPTANCE

TERMS & CONDITIONS

1. Price basis Ex-Works untill freight is specifically mentioned and described on the QUOTATION
2. Taxes included as actual.
3. Options or items not mentioned in this quoatation are not included.
4. Accepting this quote I accept terms and conditions.
5. The validity of this QUOTATION is for 30 natural days and for the quantities listed on the quote request unless otherwise noted.
6. In order to constitute the "Contract of supply" as complete, the customer will have to confirm this QUOTATION within the validity of this QUOTATION.
7. The installation charges are not included unless specifically mentioned and described on the QUOTATION.

In order to constitute the "Contract of installation" as complete, the customer will have to confirm this QUOTATION within the validity of this QUOTATION.

8. Any special request (e.g., manufacturer certification, test reports, first article inspections, special packaging, palletizing) that were not noted on the quote request may incur an additional fee.
9. Unless otherwise stated, all the prices are quoted on INR (Indian Rupees) and do include taxes.
10. Prices do not include freight unless specifically mentioned and descripted on the QUOTATION.
11. The exact shipping and insurance charges, if any, can be obtained after placing the order.
12. All bank charges, etc., will be borne by the customer unless otherwise stated.
13. The ETD is 3-4 weeks from the advance receipt date/contract documents whichever is later, nevertheless all proposed delivery dates are estimated. Upon receipt of the order, confirmed delivery dates can be obtained.
14. The customer is solely responsible for confirming the specifications, as well as determining the suitability and compatibilityapplication. in the selection of the given products for its
15. The standard packaging is included. Additional, special or extra packing will require additional fees.
16. Errors and omissions: potential suppliers/buyers will not take advantage of any apparent error or omission in the QUOTATION documents.
17. In case errors or omissions are discovered, the supplier/buyer will immediately notify the other parties.
18. Design, drawings, samples, technical date, tooling, gauges, know-how given to you by the Company on this QUOTATION, are owned by Zirkel Infraca India Pvt. Ltd., and an exclusive property and shall be retained by the Customer in safe custody and in the strictest confidentiality. The designs, drawings, samples, technical data, know-how, tooling's, gauges, etc., attached to this QUOTATION will not be allowed to be copied, duplicated, modified, passed on or revealed in any manner to any unauthorized person, outside vendor/Customer and they shall be returned to us on demand.
19. The customer will specify on the PO the technical information along with the specific measurements of the products that the company will supply In the case that the customer is not able to provide the required technical information, or wants that a company engineer to visit site for getting technical information other than the GA drawings, prior to issueing PO, the company engineer's visit will be on chargeable basis of rs 4000 /- per day *taxes and duties extra
20. The company will not be responsible for any orders placed or instructions given by any un-authorized person.
21. It is mandatory to acknowledge Zirkel Infraca supply PO and installation PO post the receipt of customer purchase order, draft of Zirkel Infraca purchase order can be accessed on our website 'www.zirkelinfraca.com/supply'

Customer signature and stamp