HAIMAVATHY PROPERTIES PRIVATE LIMITED

Corporate Identity Number : U45100MH2017PTC300045
Regd. Office: ONE BKC, A Wing 1401, Plot No. C-66, G Block, Bandra Kurla Complex, Bandra (E), Mumbai 400 051.
Tel.: 022-33965700

To,	Work Order No.: Vrindavan Project/Gate/01
M/s. NIHVA Technologies Pvt. Ltd. 187, G-Block, Thermax Chowk, M.I.D.C Chinchwad, Pune – 411019 GST No. 27AAECN0437H1ZM	**Revision No.:** 00 **Date:** 03.08.2021 **Contactors Quot. Ref:** No Regret offer dated 02.08.2021

Attention: Mr. Vijay Mahadeo Tarak
Contact: 8551093333
Email: sales@nihva.com

WORK ORDER - DO NOT DUPLICATE

In accepting this WORK ORDER, CONTRACTOR agrees to furnish the GOODS/Do WORK specified in full accordance with all conditions set forth herein and / or attachments hereto. All drawings, designs, specifications and other data prepared by OWNER and related thereto are the property of the OWNER and must be returned to OWNER upon completion by CONTRACTOR of the obligations under this WORK ORDER. The information contained herein is not to be released or disclosed for any other use or purpose other than for the execution of this WORK ORDER. It is important that CONTRACTOR signs and returns the Work Order copy within three (3) days of receipt. No other form of Order acceptance will be accepted. Failure to return the Order acceptance does not diminish the responsibilities as set forth herein, but may result in delay to any payment(s) that may be due and may be the cause for termination of this WORK ORDER.

For all correspondence, Please quote Contract/Work Order No.
For detailed commercial terms & conditions, please refer line items terms/enclosures.

WO Period: 03.08.2021 to 30.09.2021	PO Value: GST:

Total Order Value:

For other details, please refer line items.

Delivery Terms : Purchase Order for **"Design , Manufacture, Supply , Unloading , Shifting , Installation and Commissioning of Sliding type main Gates and swing type wicket gates for Vrindavan Project"** at Nepeansea Road, Mumbai
Engineer in Charge : Sh. Sudhir Kulkarni: 7738624154 / Sh. Abhijit Patil: 8452045589

Payment Terms: Refer Special Conditions of Contract

Buyer:	For Haimavathy Properties Pvt. Ltd	Contractors Acceptance
Rewa	H.L.Chokse	Sign Title Date

Haimavathy Properties Private Limited H

VRINDAVAN - MOTORIZED M.S . SLIDING GATE & WICKET GATES

Srno	Specification	NIHVA TECHNOLOGIES
1	Certification	EU Declaration of Conformity (N. 624/TUB4)
2	MOC	MILD STEEL HDG
3	No of leaves.	Single for motorized sliding door
4	Sliding Gate - Overall weight	
a	3.9 x 2 m	3395 KG
b	3.5 x 2 m	3015 KG
c	3.5 x 2 m (sliding folding manual type)	3015 KG
d	Manual swing type gate - Overall weight	225 KG
e	Manual swing type double leaf gate - Overall weight	700 kg
5	**Technical Specification**	
5.1	Design	DESIGN WITH REFERENCE TO RECEIVED REFERENCE DRAWING & ACCORDINGLY MEMBER SELECTION
5.2	Sliding Gate Frame	~~150X150X5~~ 150 x 100 x 4 mm
5.3	Sliding intermediate vertical members	100x100x3
5.4	Swing type gate main frame	~~150X150X5~~ 150 x 100 x 4 mm
5.5	Swing type gate intermediate vertical members.	100x100x3
5.6	Full Height Column with Nylon rollers (same as Gate height)	150X150X5
5.7	Bottom rail	ISMB 100 WITH ROD 20 MM WELDED
5.8	Bottom Rollers	DIAMETER 150 MM
5.9	Mounting surface columns	N/A
5.1	Drive/ Motor Specification for operation of Gate.	MAKE- NICE
5.11	Travel control system	Control unit with limit switches to sense open & close positions
5.12	Capacity	4000 KG
5.13	Working cycle	100000 cycles per motor.
5.14	Power Supply Vac (Vdc)	3 PHASE , 400V AC ,5 Hz
5.15	Absorption	1.6A
5.16	Input	3A
5.17	Torque max.	216N-M
5.18	Opening / Closing Speed	9.5M/MIN
5.19	Release system for manual opening	MECHANICAL SYSTEM
5.2	Product dimensions	580X480X240
5.21	Rack	SUTAIBLE FOR PINION MODULE 6
5.22	Control Switch	TWO STATION CONTROL , ONE AT MTOR & ANOTHER SECURITY CABIN
5.23	Safety devices	PHOTOCELL
5.24	Protection class	1 (SAFETY EARTHING IS REQUIRED)
5.25	Motor operation	PCB card is in buit in motor,
5.26	**Other Features**	
	i.	PHOTOCELL
	ii.	FLASHING LIGHT
	iii.	KEY-OPERATED SELECTOR SWITCH
5.27	Surface Finish	HDG
5.28	Safety post (to prevent overtravel)	4 NOS POST FOR GATE
5.29	Fabrication and transportation	FABRICATION NIHVA WORKSHOP, Transportation in Nihava Scope
5.3	Foundation bolt & Template for foundation	In M/s NIHVA scope.

Rewa

Haimabathy Properties Private Limited

H.L. Cholera

VRINDAVAN - MOTORIZED M.S . SLIDING GATE & WICKET GATES -					
Sr No	Item	UOM	Qty	Supply & Installation	
				Rate	Amount
	Item of work : Design , Manufacture, Supply , Unloading , Shifting , Installation and Commissioning of Sliding type main Gates and swing type wicket gates , including , scaffolding , preparation of shop drawings, etc complete.The scope shall include including straightening & bending (if required), cutting to required size, grinding, threading , drilling, welding and / or bolting of joints and completing the work as per client drawings, specifications.cleaning the surfaces by wire brushing, splices for making member length required, holding in position by guy ropes during erection with suitable temporary guys, and removing the same after placing instable position. **2Nos remote each for motorised gates. 2 nos motorised and 2 nos wicket gate is designed for future height extension of 2.5m above 2m.**				
1	**M.S. Sliding Gate (Motorised)**				
a.	3.90 x 2m (on North West Side)- clear opening	no	1	8,10,000	8,10,000
b.	3.50 x 2m (on outh West side)- clear opening	no	1	7,70,000	7,70,000
2	**Sliding & Folding (manual operation)**				-
a	5.50 x 2m (1 no on North East side)- clear opening	no	1	4,50,000	4,50,000
3	**Swing type wicket gate (manual operation)**				-
a	1.40 x 2 m (On North West side)-clear opening	no	1	85,000	85,000
b	3.50 x 2 m Double leafdoor (On South West side)-clear opening	nos	1	2,20,000	2,20,000
	TOTAL (Basic)				**23,35,000**
	Transportation				Included
	Transit insurance				Included
	Packing & Handling charges				Included
	Unloading at site with Hydra, crane etc.				Included
	Shifting Charges				Included
	Total including Transportation and Transit insurance				**23,35,000**
	GST @18 %				4,20,300
	Total including GST				**27,55,300**
	Optional Accessories				
a	Additional three station push button & limit switch	Included			
b	~~Rubber safety bar with infrared signal transmission system (Upto 2.5m in height)~~ Rewa	~~Included~~ Rewa			
	All civil works / alterations in structural wall	In client's scope			
	Terms & Conditions :				
1	**Payment Terms**	**For Supply & Installation**			
		1. 40% Advance against basic amount of W.O. (against non-dated Cheque of equal amount in the name of Issuing company valid till material received at site) 2. 50% Immediate after delivery (within 15 days) 3. 5% against installation 4. 5% Retention for 12 months from the date of Installation (can be released against submission of PBG)			
2	Work completion period	6-8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.			
3	Warranty	24 months from date of supply for Fabricated gates and 12 months for Motor.			
4	Installation and mobilization of manpower - Period	2 DAYS after material delivery at site.			
5	Storage & Custody of Material	M/s NIHVA scope			
6	Crane/Hydra/forklift/vehical etc at the time of Installation and Internal Shifting at site	M/s NIHVA scope			
7	Scaffolding if required	M/s NIHVA scope			
8	Electrical power and water supply	Will be provided by Client at one location.			
9	Conduit , cables , water supply piping (whereever required)	M/s NIHVA scope			
10	Detailed Drawings / Shop drg	M/s NIHVA scope			
11	Test Certificate	Will be provided by M/s NIHVA			
12	Offer validity	Validity of Offer is 15 days from the date of quotation			

Rewa

Haimavathy Properties Private Limited

H. L. Cholera