NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1878R4 **Date : 24.08.2019**

SCON Projects Pvt. Ltd
Office No.1A, Harshal Corner, Plot No.5, Survey
No.78, Left Bhusari Colony, Paud Rd., Kothrud
Pune - 411038 .

Kind Attn: Mr. Kamalesh Bagade
Email: kamleshb@sconprojects.com
Contact No: 8308809561

Project Name And Location : Innovatec india pvt. Ltd.

Subject : Quotation for Sectional Door, Dock Leveller Boom Barrier and Bollards .

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**ASSA ABLOY-ALBANY Sectional Door** **(Supply & Installation)**				
1	Size : (W) 3000 mm x (H) 3500 mm (Vertical Lifting Sectional Door with Fire alarm interlockng system)	3	No	325,000	975,000
2	Size : (W) 3000 mm x (H) 4500 mm (Vertical Lifting Sectional Door with Fire alarm interlockng system)	3	No	340,000	1,020,000
3	Size : (W) 5000 mm x (H) 3500 mm (Vertical Lifting Sectional Door with Fire alarm interlockng system)	1	No	398,000	398,000
4	Size : (W) 6500 mm x (H) 4500 mm (Vertical Lifting Sectional Door with Fire alarm interlockng system)	1	No	565,000	565,000
5	Size : (W) 6500 mm x (H) 3500 mm (Vertical Lifting Sectional Door with Fire alarm interlockng system)	1	No	521,000	521,000
B	**Dock Leveler (NIHVA Make)** **2 cylinder for Deck & 1 cylinder for LIP Operator by Standard Control Panel (Deck Up/Down/Lip Up/Down) Rubber Bumpers.**				
1	**Dock Levelers Capacity 10 Ton** Size : (W) 2200 mm X (L) 3000 mm Supply + Installation	3	No	200,000	**600,000**
	Total				**600,000**
C	**Assa Abloy Make Dock Shelter** **Rectractable Dock Shelter** **(100% Imported products from Europe).**				
1	Size : (W) 3400 mm X (L) 3400 mm Supply + Installation	3	No	90,000	**270,000**
	Total				**270,000**
D	**Boom Barrier** **(L)4000 mm** **Each Boom Barrier Set include:** **MICHELANGELO BT A Barrier-1No.(Opening Time- 6S)** **• Round Boom First part-1No.** **• Round Boom Second part- 1 No.** **• Anchor Base- 1No.** **• MOB. Boom Rest-1No.** **• Rubber Safety Profile- 1No.** **• OMEGA AT Acce. - 1No.** **• Transmitter with Channels- 1No.** **• Push Button** **(Supply + Installation)**				
1	Size : 4.5 Mtr	2	No	80,000	**160,000**
	Total				**160,000**

E	**Bollard Barriers** **Automatic Electromechanical bollard** **Size - diameter 200 mm and height 700 mm.** **• Control unit** **• Push Button** **(Supply + Installation)**				
1	Size - 200 dia and 700 mm ht	11	No	250,000	**2,750,000**
	Total				**2,910,000**

GST PUNE:	**27AAECN0437H1ZM**

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material.
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1 Price : At Site
2 P & F Charges : Nil
3 Freight Notes : Nil
4 Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
5 Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6 Insurance : Extra As applicable
7 Tax : GST@18%
8 Validity : Validity of Offer is 15 days from the date of quotation
9 Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil** on **8551096333** for any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd