NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

ATC Tires Pvt. Ltd.
Dahej Gujrat

Date : 05.07.2022
Quote NO : RR_22.23.0051
Kind Attn : Mr. Yuvraj Jadhav
Email Id : yjadhav@yokohama-oht.com
Contact No: 99230 02740

Project Name & Location: ATC Tires Pvt. Ltd., Dahej Gujrat

Subject : Commercial Offer for VRF AIR CONDITIONING SYSTEM

Dear Sir / Ma'am,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Techno-Commercial Offer	1
B.	General Conditions	2
C.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size	Qty	Supply and Installation Charges in INR	
			(Nos)	Unit Charges	Total
1	**SUPPLY OF VRF AIR CONDITIONING SYSTEM** • VRF outdoor unit • Double skin floor mounted vertical type air handling unit •Corded remote controller• Ref. joints for IDU•Ref. joints for ODU• EEV kit & Communication kit	• 8400 (W) X 14200 (L) X 3500 (H) mm	1	55,60,000	55,60,000
2	**INSTALLTION OF VRF AIR CONDITIONING SYSTEM** • VRF outdoor unit • Double skin floor mounted vertical type air handling unit•Corded remote controller• Ref. joints for IDU•Ref. joints for ODU• EEV kit & Communication kit • All refrigerant piping with nitrile rubber insulation between indoor & outdoor units of copper pipes properly supported • Communication Control cables between indoor and outdoor unit laid in PVC conduit pipe and clamped • Rigid PVC Drain Piping with Nitril Rubber Insulation. • Testing & Commisioning charges alongwith topping-up of R-410A Refrigerant Gas.• Galvanized Rectangular Ducting • Thermal Insulation with Class "O" Nitrile Rubber with Factory Laminated Alu. • Foil Acoustic Insulation with Open Cell Nitrial Rubber Insulation • Duct Flexible Canvas Connection • Aluminium Powder Coated Grill • Aluminium Powder Coated VCD • Electrical Control Panel for AHU, Veriable Frequency Drive for AHU Operations with Bypass Starter, HMI Display, Heater Operations etc.•All Electrical Cabling from AC Equipment to Electrical Panel up to 5 Meter (Main Incoming Cable to Electrical Panel will be in Client's Scope.)	• 8400 (W) X 14200 (L) X 3500 (H) mm			
3	**Supply, Installation, Testing & Commisssioning of Factory Fabricated PUF Insulated Double Skinned Panel with Fabrication Supports and Section with Thermal break profile at corners & at joints for Tyre test cell internal covings with 0.8mm thick precoated galvanised sheet outside & 0.8mm polished GI sheet inside**	1000	Sqft	1,500	15,00,000
4	**MS Modification work of Existing Tyre testing cell including Dismantling of MS Fabrication casing Doores, etc with Arc Welding, Re-installation, assembling, painting, Etc.**	3500	Kg	60	2,10,000
			Total		**72,70,000**
			Total Without Taxes		**72,70,000**
5		GST Extra @ 18%			**Extra At Actual**
6		P&F Charges @ 3%			**Extra At Actual**
7		Transportation Charges			**Extra At Actual**
8		Unloading Charges @ Site			**In Client Scope**
9		Note:			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) General Conditions

1. Continuous uninterrupted access to installation section or as agreed seperately.
2. Provision of 230 V power supply for hand tools.
3. A dry and secure area, not in direct sunlight is to be provided for storage of product component.
4. Access to site between 7 am to 8 pm should be provided.
5. Any storage costs for material due to delay outside of NIHVA, will be in client scope.
6. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly.
7. Installation will start after receiving of Site Readiness Photographs or written Email communication.
8. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.
9. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
10. If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.
11. Insulation of exposed roof with 2" thick Thermocole In client scope
12. Electrical main incoming cable terminating on individual of all A/C units, together with earth. Main incoming Copper Armored Cable, ELCB, MCB, MCCB etc.
13. Safe custody and lockable storage space required at site
14. Wooden frames for fixing of grills & diffusers is in client scope.
15. Wooden Boxing or Trap door required for all indoor unit in client scope.
16. Provision of drain points within vicinity of indoor unit.
17. Any modification in the existing false ceiling and making of new false ceiling not included in the offer.
18. Any items not specifically mentioned in the scope of work not included.
19. Water Supply for any work at site will be in customer's scope.
20. Authorized Work Permit to do work at site will be in customer's scope
21. Any revision/changes in a work done as per approved drawing. If any will be charged extra as actual.
22. After 1 year warranty, Non comprehensive AMC will be provided by NIHVA, at an additional cost.

Note: Please find below List which are in Client Scope

Sr. No		Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

C) Terms & Conditions

Price :	Ex Works Pune.
Delivery :	10-12 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.
Payment :	80% Advance along with Confirmed Purchase Order. 15% Along with Approval of Drawing and before start a Production. 5% Against Material Delivery.
Validity :	Validity of Offer is 7 days from the date of quotation.
Billing:	Mentioned quantity in BOQ is approximate, final billing will be made as per actual installation made on site.
Warranty :	12 months from the date of supply.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd