Sales Quotation

Quotation No - SQT/19-20/1518R1 **Date : 27.04.2019**

Rohan Builders (India) Pvt. Ltd.
1 Modibaug,Commercial Building, CTS NO.2254,
Ganeshkhind Road, Shivaji Nagar, Pune - 411 016.

Kind Attn : Mr. Mayuresh Prabhune
Email ID : mayuresh.prabhune@rohanbuilders.com
Contact No : 70284 77336

Project Name And Location : A Raymond

Subject : Quotation for High Speed Doors, Fire Rated Rolling Shutter, Rolling Shutter, Fire Door,Sliding Door ,Tripod Turnstile and Dock Leveller, Steel Door.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**ASSA ABLOY (Albany) Rapid Roll Up Door RR300+AL** **(100% Imported – made in Germany)** **(Supply + Installation)**				
Door panel:	Transparent PVC with Red (RAL 3002) reinforcement stripes.				
Barrel:	Aluminium, anodized with shafts made of galvanized steel				
Wind Reinforcement:	Door Panel wind tabs for improved wind resistance				
Vision Window	Vertical Transparent Vision panel				
Side Frames:	Aluminium profiles, anodised				
Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.				
Bottom beam:	Anodized extruded aluminium.				
Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s				
Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns				
1	Size (W) 2400 mm x (H) 3000 mm	4	No	639,000	2,556,000
2	Size (W) 1800 mm x (H) 3000 mm	2	No	625,000	1,250,000
3	Size (W) 3000 mm x (H) 3000 mm	1	No	653,000	653,000
				Total	4,459,000
B	**Motorized Rolling Shutter** **Technical Specifications:** **• MS Slat : 1.0 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 2.5 mm Thick MS Guide** **• Hood Cover & Motor Cover : 0.9 mm Thick GI material** **• Indirect Drive** **• With Painting** **(Supply + Installation)**				
1	Size (W) 5000 mm x (H) 7000 mm	2	No	244,000	488,000
2	Size (W) 3000 mm x (H) 3000 mm	3	No	103,000	309,000
3	Size (W) 5000 mm x (H) 3000 mm	2	No	134,000	268,000
				Total	1,065,000
C	**ASSA ABLOY-BESAM-Automatic Sliding Door SL 500** **100% imported from Sweden** **Specifications :** 1. Main power supply 2. Operator type- Bi part operator/single slide 3. User interface- Auto Partial/Auto/one way/closed including LED status 4. Battery- Battery 12 V power fail open 5. open Operator lock- Electric lock (fail safe) 6. Glass : 10mm thick 7. Sensor for both side application				
1	**Size** : (W) 1220 mm x (H) 2800 mm Supply + Installation	1	No	190,000	190,000
D	**Tripod Turnstile:** **(Supply + Installation)**				
	• It has fault self-test and alarm prompt function, which is convenient for users to maintain and use. **• Can be connected to any control device output control signal or button or remote control, to achieve single bidirectional control pass.** **• The Tripod may be programmed for uni-direction access & bi-directional access as well.** **• Hold Open Time: On flashing a card the Tripod arm must be moved to initiate action. If there is no action initiated the arm locks itself after a 10 second hold open time.** **• Light indication: High-brightness traffic light status indication, guide the passage.** **• Anti-tailing function: The design is such that tailgating is negated. However, if there is an attempt to pass through after an operation is completed the arm locks and initiates an alarm condition if the thrust continues.** **• Fire input: Fire input connection may be terminated for initiation of fail-safe operation during emergency.** **• Input Memory function: In case of heavy traffic, the system can accept more than one card for quick processing of traffic.** **• Anti-reverse function: When the reversal occurs during the passage, the brake lever will automatically start the reverse thrust blocking and issue an alarm. After the external force disappears, the passage will automatically resume.** **• Drop Arm Function: The Tripod Arm drops automatically during emergency and when power is cut. On resumption of power/normalcy the Tripod arm is deployed in blocking position and is then ready for normal operation.** **• Dynamic reminder: On receiving a signal for access the arm moves about 5 degrees, and thereafter a soft touch rotates the arm to complete an access and stops.**				
1	Turnstile	1	No	155,000	155,000

E	**Dock Leveler (NIHVA Make)** **2 cylinder for Deck & 1 cylinder for LIP Operator by Standard Control Panel (Deck Up / Down / Lip Up / Down) Rubber Bumpers.**				
1	**Dock Levelers Capacity 10 Ton** Size : (W) 2030 mm X (L) 2700 mm (Supply + Installation)	1	No	**220,000**	220,000
1	**Dock Levelers Capacity 5 Ton** Size : (W) 2030 mm X (L) 2700 mm (Supply + Installation)	1	No	**215,000**	215,000
	Total				435,000

F	**Steel Door** **Steel Door with Rockwool infill. GI Sheet Doors panel with 44mm thick & 0.8mm Face Sheet. Frame 1.2mm thick and 100X70mm Jamb depth & width**				
1	**Single leaf Door** **Size : (W)900 mm x (H)2400 mm**	7	No's	9,400	65,800
Accessories	SS Ball Bearing Hinge 102X76X3mm - Make Dorma	28	No's	300	8,400
	Door Closure	7	No's	2,000	14,000
	Vision Panel – 300 x 300 mm	7	No's	2,900	20,300
	Panic bar- Single Point	7	No's	5,300	37,100
	External Trim	7	No's	4,700	32,900
	Installation charges for above Doors	7	No's	6,500	45,500
	Total (Supply + installation)				**224,000**

G	**Steel Door** **Steel Door with Rockwool infill. GI Sheet Doors panel with 44mm thick & 0.8mm Face Sheet. Frame 1.2mm thick and 100X70mm Jamb depth & width**				
1	**Double Leaf Door** **Size : (W)1800 mm x (H)2400 mm**	7	No's	18,800	131,600
Accessories	SS Ball Bearing Hinge 102X76X3mm	56	No's	300	16,800
	Door Closure – Ryobi-8803	14	No's	2,000	28,000
	Vision Panel – 300 x 300 mm	14	No's	2,900	40,600
	Panic Bar	14	No's	13,200	184,800
	External Trim	7	No's	4,700	32,900
	Flush Bolt	14	No's	1,200	16,800
2	Installation charges for above Doors	7	No's	6,500	45,500
	Total (Supply + installation)				**497,000**

H	**Steel Door** **Steel Door with Rockwool infill. GI Sheet Doors panel with 44mm thick & 0.8mm Face Sheet. Frame 1.2mm thick and 100X70mm Jamb depth & width**				
1	**Double Leaf Door** **Size : (W)1200 mm x (H)2400 mm**	4	No's	12,500	50,000
Accessories	SS Ball Bearing Hinge 102X76X3mm	16	No's	300	4,800
	Door Closure – Ryobi-8803	4	No's	2,000	8,000
	Vision Panel – 300 x 300 mm	4	No's	2,900	11,600
	Panic Bar	4	No's	13,200	52,800
	External Trim	4	No's	4,700	18,800
2	Installation charges for above Doors	4	No's	6,500	26,000
	Total (Supply + installation)				**172,000**
I	**2 hrs Fire Door**				
1	**Single leaf Door** **Size : (W)1000 mm x (H)2400 mm**	10	No's	15,300	153,000
Accessories	SS Ball Bearing Hinge 102X76X3mm - Make Dorma	40	No's	300	12,000
	Door Closure	10	No's	2,000	20,000
	Vision Panel – 200 x 600 mm	10	No's	4,600	46,000
	Panic bar- Single Point	10	No's	5,300	53,000
	External Trim	10	No's	4,700	47,000
	Installation charges for above Doors	10	No's	6,500	65,000
	Total (Supply + installation)				**396,000**
J	**2 hrs Fire Door**				
1	**Double leaf Door** **Size : (W)1800 mm x (H)2400 mm**	2	No's	27,400	54,800
Accessories	SS Ball Bearing Hinge 102X76X3mm - Make Dorma	16	No's	300	4,800
	Door Closure	4	No's	2,000	8,000
	Vision Panel – 200 x 600 mm	4	No's	4,600	18,400
	Panic bar- (Double Point)	4	No's	13,200	52,800
	External Trim	2	No's	4,700	9,400
	Flush Bolt	4	No's	1,200	4,800
	Installation charges for above Doors	2	No's	6,500	13,000
	Total (Supply + installation)				**161,200**

K	**Fire Sliding Door**				
1	Size : (W)3000 mm x (H)2400 mm **(Supply + Installation)**	1	No	190,000	190,000
	Total				**190,000**
L	**2 Hrs. Fire Rated Rolling Shutters** **•Shutter Slats: Zinc coated steel solid slats** **•Slat Thickness: 1.0mm thick** **•Shutter Guide: Galvanize Steel, 3mm thick** **•Operated by: Motor with one unit push button switch & manual override**				
1	Size : (W)3000 mm x (H)3000 mm **(Supply + Installation)**	1	No	275,000	275,000
	Total				**275,000**

GST Pune	**27AAECN0437H1ZM**	**Grand Total**	**8,219,200**

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material.
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	11-12 weeks for High Speed Door, Sectional Door and 4 -5 weeks for Steel Door and Telescopic Gate from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Insurance**	:	Extra As applicable
8	**Tax**	:	GST Extra @ actual
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat** on **7219207333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka
7219206333
For NIHVA Technologies Pvt Ltd