Client Name	Instafarm Products Pvt. Ltd.
Location	Mahesana, Gujarat

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

PRODUCT DATA SHEET		
Product Type		PIZZA
Product temp.	Process Line	(50 - 60) °C
	Packaging Line	(-18 to -20) °C
Product Size (Pizza)	Length (mm)	187
	Width (mm)	187
	Height (mm)	32
	Wt.(gm)	300
	Line capacity	60 pcs/min
Product Size (Packaging Line- Tray)	Length (mm)	175
	Width (mm)	125
	Height (mm)	75
	Wt.(gm)	165
	Line capacity	100 pcs/min
Carton Size (Lx B x H mm)		200 x 600 x 155
Carton Unit wt.		6-8Kg
Pouch Size & wt.		225 X 200

EQUIPMENT DETAIL (KMPL SUPPLIES)- All Support Structure should be in Stainless Steel & Belt will be in Food Grade

Drg. S.no	Equipment Type	Specification (Belt Width x C/C Length)	Feed From	Discharge To	Belt Type	Remarks	Qty.	Unit Price	Total Price
1	Horizontal Conveyor-1	600 x 1500 Lg.	Grote Machinery	Freezer feeding conveyor	Modular	With product diverter (Pivot)	1	2,50,000	2,50,000
2	Freezer Feeding conveyor	600 x 2000 Lg.	Horizontal Conveyor-1	Freezer	Wire belt	with SS Partition	1	3,00,000	3,00,000
3	Freezer Outfeed Conveyor (Spiral)	600 (B/w)x 3100	Freezer	Cutting Machine / Product pick-up conveyor	Modular	n/a	1	6,00,000	6,00,000
4	Product Collection Conveyor	600 x 4000 Lg.	Cutting Machine/ Freezer outfeed conveyor (Spiral)	Manual Pick up	Modular	n/a	1	4,50,000	4,50,000
5	Tray/Pouch Transfer Conveyor	450 x 4300 Lg.	Manual Placing/ Pouch sealing machine	MD & check weigher	Modular	n/a	1	4,25,000	4,25,000
6	SLEEVE / HOTBOX Transfer Conveyor	450 x 1700 Lg.	MD & check weigher	Manual Pick up	Modular	n/a	1	2,75,000	2,75,000
7	Carton Transfer Conveyor	450 x 6910 Lg.	Manual Placing	Carton check weigher & rejector	Modular	n/a	1	5,50,000	5,50,000
8	Date Coder Conveyor	450x1000 Lg.	Carton check weigher	Roller Conveyor	Modular	n/a	1	3,40,000	3,40,000
9	Roller Conveyor	450 x 1000 Lg.	Date coder	Carton sealing machine	SS-Roller	n/a	1	3,75,000	3,75,000
10	BUFFER CONVEYOR (Pouch date coding)	450 x1000 Lg.	Manual Placing	Manual Pick up	Modular	n/a	1	3,06,035	3,06,035
11	Control Pannel	1500 x 1400					1	11,75,000	11,75,000
						TOTAL PRICE (INR)		**50,46,035**	

Terms & Conditions

Price : Ex Works Pune

Delivery : 10- 12weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

General Conditions

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment	In Client Scope
7	Conduits, Cables required	In Client Scope

GST	**18% Extra as applicable**
P&F	**3% Extra as applicable**
Installation Charges in INR	**450000 Extra**
Transit Insurance Scope	Client Scope
Installation & Commissioning	NIHVA Scope