Quote

NIHVA TECHNOLOGIES PVT. LTD.

Quote No: 1663 R1 **Date10/21/2019**

LM Wind Power Blades

-
-

Kind Attention: SantoshNaik

Phone: (988) 094-2200
Email: sang@lmwindpower.com

Project Name And Location: Spare-installation

Subject : Quote for -Motorised Rolling Shutter, Sectional Doors and High Speed Doors

Dear Sir,

Thank you for your opportunity and trust shown on “NIHVA.” your preferred partner for innovative solutions. This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer

Sl.No.	Description	Price	Qty	Total
1.	Double Wall Motorised Rolling Shutter - Direct Drive Size :(W) 4000 mm x (H) 4000 mm Technical Specifications : • Direct Drive • PCGI Slat : 19 mm Thick • Profile : Curved Type Profile with heavy duty Shaft • Guide : M S Guide • Hood Cover & Motor Cover : GI Powder Coated • With Push Button and Flashing Light (Supply + Installation)	₹ 327,000.00	2	₹ 654,000.00
2.	ASSA ABLOY Make Motorized Sectional Door 100 % Imported from Europe Specifications : Lifting : Standard Lift Windows : 2 nos. Accessories : Motor and Control with all safety features Extra Push Button, Remote and Receiver Size : (W) 6000 mm x (H) 7500 mm (Supply + Installation)	₹ 1,260,000.00	6	₹ 7,560,000.00
3.	ASSA ABLOY Make Motorized Sectional Door 100 % Imported from Europe Specifications : Lifting : Standard Lift Windows : 2 nos. Accessories : Motor and Control with all safety features Extra Push Button, Remote and Receiver Size :(W) 4000 mm x (H) 4000 mm (Supply + Installation)	₹ 396,000.00	3	₹ 1,188,000.00

Quote

NIHVA TECHNOLOGIES PVT. LTD.

Quote No: 1663 R1				Date10/21/2019
Sl.No.	**Description**	**Price**	**Qty**	**Total**
4.	High Speed door HS8010P ASSA ABLOY make High Speed Door - HS8010P Suitable for Outside operation Operating speed : opening: up to 2,4 m/s closing: 1,2 m/s Wind load resistance EN 12424 : class 3 (700 N/m2) ,class 4 (1000 N/m2) Water penetration, EN 12425 : class 2 (50 N/m2) Size : (W) 4000 mm x (H) 4000 mm (Supply + Installation)	₹ 789,000.00	3	₹ 2,367,000.00
5.	High Speed door HS8010P ASSA ABLOY make High Speed Door - HS8010P Suitable for Outside operation Operating speed : opening: up to 2,4 m/s closing: 1,2 m/s Wind load resistance EN 12424 : class 3 (700 N/m2) ,class 4 (1000 N/m2) Water penetration, EN 12425 : class 2 (50 N/m2) Size : (W) 3000 mm x (H) 3000 mm (Supply + Installation)	₹ 719,000.00	5	₹ 3,595,000.00
6.	Sectional Door 100 % Imported from Europe Specifications : Lifting : Standard Lift Windows : 2 nos. Accessories : Motor and Control with all safety features Extra Push Button, Remote and Receiver Size :(W) 3000 mm x (H) 3000 mm (Supply + Installation)	₹ 364,000.00	1	₹ 364,000.00

Sub Total	₹ 15,728,000.00
Tax	₹ 0.00
Grand Total	**₹ 15,728,000.00**

Quote

NIHVA TECHNOLOGIES PVT. LTD.

Quote No: 1663 R1 **Date10/21/2019**

General Prerequisites Required at Site
1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required.
5. Scaffolding require for Installation it is in client scope.

Limit of Supply
1. Provide place to store the material to be installed.
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation.
4. Provide change & rest room for the workers.

Quote/Supply is based on
1. BOM is calculated as per standard quantity measurement.
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements.

The supply included only those mentioned in the quote & does not include.
1. Unloading from truck placement on site.
2. Electrical connection for control panel.

Client Scope
1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope.
2. Any civil / masonry/structural work required to support are in client scope.
3. All structure support is in client scope.
4. NIHVA Will provided structure drawing only if required.
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms & Conditions
1. **Price:** Ex. Works Pune
2. **P & F Charges:** Extra @3%
3. **Delivery:** 5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
4. **Payment:** 80% Advance along with confirmed purchase order& Balance before dispatch.
5. **GST:** Extra @18%
6. **Validity:** Validity of Offer is 15 days from the date of quotation
7. **Warranty:** 12 months from the date of supply.

Please feel free to Contact Mr. Shashank Jagtap on 7410169333 For any further Clarification /Information in this Concern.

With Best Regards
Monika Kadam
8551059333
For Nihva Technologies Pvt Ltd