**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Nima Enterprises**
Ahmedabad

**Date :** 08.01.2022
**Quote NO :** **MHE_21.22.0048R**
**Kind Attn :** Mr. KETAN RUPAREL
**Email Id :** ketan@nimaenterprises.com
**Contact No:** 9930258280

**Project Name & Location: Nima Enterprises, Ahmedabad**

**Subject : Quotation for Loading/Unloading Conveyor**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 2 |
| D. | Terms & Conditions | 2 |

**A) Commercial Offer**

| Sr No | Description | Qty | Supply Charges in INR | | Installation considering 03 people for 03 days per conveyor in INR | |
|---|---|---|---|---|---|---|
| | | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Truck Loader/Unloader Conveyor**<br>• Total Length- 12 mtr<br>• Capacity- 20-30 boxes/min | 1 | 8,50,000 | 8,50,000 | 35,000 | 35,000 |
| 2 | **Take Up Conveyor**<br>• Inclined Height: 5.5 mtr | 1 | 5,75,000 | 5,75,000 | 35,000 | 35,000 |
| | | Total | | 14,25,000 | | 70,000 |
| 3 | GST Extra @ 18% | 18% | | | | Extra At Actual |
| 4 | P&F Charges | 3% | | | | Extra At Actual |
| 5 | Transportation Charges | | | | | Extra At Actual |
| 6 | Insurance Charges | | | | | Extra At Actual |
| 7 | Unloading Charges @ Site | | | | | In Client Scope |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Truck Loading/Unloading Conveyor**

| Sr. No. | Parameters | Specification |
|---|---|---|
| 1 | Material to be conveyed | Bags/Boxes |
| 2 | Maximum Weight of Box/Bag | 22 Kg max. |
| 4 | Capacity | 30 boxes/min |
| 5 | Size of Belt | 750 mm |
| 6 | Belt Type | 2 Ply 3.2 mm PVC |
| 7 | Conveyor Type | Collapsible boom type hinged Telescopic belt conveyor |
| 8 | Length Of Conveyor | Fixed Length : 6000 mm<br>Expanded Length : 6000 mm<br>Total : 12000 mm |
| 9 | Main Body Of Conveyor | MS Powder coated |
| 10 | Belt Drive | 3 HP [ With Bonfiglioli Gearbox] |
| 11 | Working Height | 1050 mm |
| 12 | Lifting Mechanism | Hydraulic power packs |
| 13 | Drive Motor & Gear Box | Bonfiglioli |

**Take Up Conveyor**

| Sr. No. | Parameters | Specification |
|---|---|---|
| 1 | Material to be conveyed | Bags/Boxes |
| 2 | Maximum Weight of Box/Bag | 22 Kg max. |
| 3 | Capacity | 10 bags/min |
| 4 | Size of Belt | 750 mm |
| 5 | Belt Type | PVC belt |
| 6 | Inclined Height | 5.5 mtr |
| 7 | Length Of Conveyor | 9 mtr |
| 8 | MOC | MS Powder coated |

**C) General Conditions**

1. Installation will start after receiving of Site Readiness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. After 1 year warranty, Non comprehensive AMC will be provided by NIHVA, which will cost you extra.

**D) Terms & Conditions**

**Price** : Ex Works Pune.

**Delivery** : 8-10 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance 20% against readiness of material before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation.

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Vijay Tarak on 855 109 3333**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd