WORK ORDER

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Client
SPACONS EPC Pvt.Ltd.
Address:
52 & 53, 1st Floor, Aditya Shagun Mall, NDA-Pashan Road, Bavdhan, Pune–411021

PO Number:	Faurecia/118/20-21-12	W. O. no-	SO/20-21/044
PO Dated :	21.10.2020	W. O. Date	22.10.2020
PO Received Date:	22.10.2020	Sales Co ordinator	Smita Khare
Ref. Quotation:	SQT.20.21.2720R	Front Sales Person	Sneha Bharane

Dispatch Address:

M/S SPACONS EPC PVT LTD
C/o Faurecia India Private Limited
P-5,Building E,KSH Multi-Model Logistic & Ind.
Park,Chakan Phase-II, Khalumbre, Tal- Khed
Pune 410501 India
Contact Person:- Sachin Autade (Mob No - 8766745020)

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Rate	Amount	Dwg. Approval
1	NIHVA Make GI Motorised Rolling Shutter	G I Motorised Rolling Shutter - Indirect Drive Motorised Rolling Shutter with GI Laths with thickness of 1mm. Mounting Location Area:- Inside area Mounting Surface : Side Brackets: Optional = On Concrete Curtain Panel:- The Panel made of 1.0mm thick MS Curtain Panel Size:- 75mm Wide Curtain Profile:- Curved Bottom Profile:- MS Plate 140 mmX 2.5mm thick Side Guide Profile:- MS U Shaped profile 65mm- 150mm x 3mm thick (as per opening width dimension) Roller Shaft:- MS Tubular pipe with flange & Machined shaft at the ends Pipe dia- 100 to 300mm as per w x h Side Brackets:- MS Plate 3mm to 10mm thick, as per the Opening dimension Hood Cover:- Made of GI sheet thickness 0.9 mm GF mm with 25X25X3mm StiffnerSurface Finish:- Powder Coated Drive Unit and Mounting Type : Indirect Drive, Electric Motor - Direct Mounting - Sprocket chain arrangement 3 Station Push Button : Included					
		(W)4500 mm X (H)5000 mm	No.	1		-	
		Installation for above shutter	No.	1		-	

A) Commerical Terms

1)	**Payment Terms:**	40% Advance along with PO against PI ; 40% against readyness of material before dispatch; 20% against Installation within week
2)	**Delivery Date as per PO:**	1 week after PO issue and drawing approval
3)	**Transportation:**	NIHVA Scope
4)	**P&F Charges:**	NA
5)	**Loading:**	NIHVA Scope
6)	**Unloading:**	Client Scope
7)	**Lifting Equipments:**	Client Scope
8)	**Warranty:**	12 months from the date of supply
9)	**Height arrangement:**	Client Scope
10)	**Electricity Supply:**	Client Scope
11)	**GST:**	Extra@18%
12)	**Installation Scope:**	NIHVA
13)	**Mode of import:**	NA
14)	**HSS:**	NA
15)	**Documentation Required:**	Standard Handover Documents

Certified that the above work order finalised in presence of:

	AGM	SALES	PROJECT	PPC	DESIGN	Date & Time
	A. K.	V.T.	S. P.	S.B	P. A.	