NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Huhtamaki PPL Ltd
Village Ransai, KM.16,
Khopoli - Pen Road,
Taluka : Khalapur, Dist - Raigad-402107

21.12.2020
SQT.20.21.2895
Mr. Dipesh Rathod
dipesh.rathod@huhtamaki.com
8007763489

Project Name & Location: Khopoli

Subject : Quotation for Motorised Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
	Option A	Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	GI Motorised Rolling Shutter - Direct Drive with Powder Coating	2500	2000	2	139,625	279,250	15,000	30,000
	Total					279,250		30,000
	P&F Charges	3%				8,377.50		
	Total without Taxes					287,628		30,000
	GST Extra @ 18%					51,772.95		5,400
	Total with Taxes					339,400.45		35,400
	Option B							
2	GI Motorised Rolling Shutter - Direct Drive with Bare Finish	2500	2000	2	124,625	249,250	15,000	30,000
				Total		249,250		**30,000**
3			P&F Charges	3%		**7,477.50**		
			Total Without Taxes			**256,728**		
			GST Extra @ 18%	18%	-	46,210.95		5,400
			Total With Taxes		**-**	**302,938**		**35,400**
3			Transportation Charges		**Extra at Actual**			
4			Unloading Charges @ Site		**Client Scope**			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

G I Motorised Rolling Shutter

Sr. No	Description	Specifications
1	Description:	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 140 mm x 2.5 mm thick
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm
12	Surface finish	Powder coated
13	Drive Unit & Mounting Type	Electric Motor - Direct Drive
14	3 Station Push Button	Included
15	Rubber Bottom Profile	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required for Rolling shutter will be in Client scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 4-5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd