NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Viran
Bangalore

Project, Location : Bangalore

Date : 05.01.2021
Quote NO : SQT.20.21.2929
Kind Attn : Mr. Viran
Email Id : alfvsnl@gmail.com
Contact No: 9845003099

Subject : Quotation for Cantilever Gate and Motorized Swing Gate.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Cantilever Gate**	5180	2440	1	372,000	372,000	20,000	20,000
2	**Motorized Bi-parting Swing Gate**	3506	2440	1	182,000	182,000	20,000	20,000
	Total			**2**		**554,000**		**40,000**
3	P&F Charges			3%		16,620		
	Total Without Taxes					570,620		**40,000**
	GST Extra @ 18%			18%		102,711.60		7,200
	Total With Taxes					**673,332**		**47,200**
4	Transportation Charges					**Extra at atcual**		
5	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA make – Cantilever Gate

Sr. No	Specification	Motorised Single Leaf Cantilever Gate
1	Door type	Motorised Single Leaf Cantilever Gate
2	Clear Opening gate dimension	5180 x 2440 mm
3	Master Leaf Size	8420 X 2440 mm
4	Opening Direction	Horizontal - from left to right or reverse
5	Outer Tube	72 X 72 X 3.2 MM THK SQ. TUBE
6	Inner Tube	25 X 25 X 2.6 MM THK SQ. TUBE
7	Gap Between Tubes	125mm
8	Post Tube	72x72x3.2 MM
9	Design Pattern	Standard Tubular Design Pattern
10	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
11	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Operation	By Cantilever Mechanism
13	Operating Switch	Push Button from inside
14	Safety	Photocells, Flashing Light
15	Civil work	Client scope

NIHVA make – Motorized Swing Gate

Sr. No	Specification	Motoriszed Bi-Parting Swing Gate
1	Clear Opening gate dimension	3506 x 2440 mm
2	Master Leaf Size	1665 X 2440 mm
3	Opening Direction	left to right or reverse
4	Outer Tube	72 x 72 x 3.2 mm THK SQ. TUBE
5	Inner Tube	25 x 25 x 2.6 mm THK SQ. TUBE
6	Gap Between Tubes	125mm
7	Design Pattern	Standard Tubular Design Pattern
8	El motor make	BFT – Italy (100% imported)
9	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
10	Civil work	Client scope
11	Emergency Operation	Manual after turn the switch

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bikas Sahu on 8530926333** For any further Clarification /Information in this Concern.

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd