NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Smith Structures India Pvt. Ltd.
Ahmedabad

Date : 27.02.2021
Quote NO : SQT.20.21.3062
Kind Attn : Atul Patil
Email Id : atul@smithstructure.com
Contact No: 9860798510

Project Name & Location: Mundra

Subject : Quotation for 2 Hrs fire rated Rolling Shutter , Steel & Fire Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**2 Hrs Fire rated Rolling Shutter - Tracker factory**	6000	6000	4	567,000	2,268,000	15,000	60,000
2	**2 Hrs Fire rated Rolling Shutter - Store Building**	6000	6000	3	567,000	1,701,000	15,000	45,000
3	**Normal Steel Door - Tracker factory**	1000	1800	5	34,000	170,000	8,000	40,000
4	**Normal Steel Door - Tracker factory**	1200	2100	10	42,000	420,000	8,000	80,000
5	**2 Hrs Fire Door - Tracker factory**	1200	2100	10	59,000	590,000	8,000	80,000
6	**Normal Steel Door - Store Building**	2400	2100	5	60,000	300,000	8,000	40,000
7	**Normal Steel Door - Store Building**	1200	2100	5	42,000	210,000	8,000	40,000
				Total		**5,659,000**		**385,000**
	P&F Charges on Total Supply Value			3%		**169,770**		
	Total Without Taxes					**5,828,770**		**385,000**
	GST Extra @ 18%			18%		1,049,178.60		69,300
	Total With Taxes					**6,877,949**		-
	Transportation Charges					**Extra at actual**		
	Unloading Charges @ Site					**In client scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

2 Hrs Fire Rated Rolling Shutter





2 Hrs. Fire Rated Rolling Shutters - 100% IMPORTED

- **Shutter Slats: SKB-F7D Double Walled Roll Form Steel with Rockwool Infilled**
- **Slat Thickness: 1.0mm thick**
- **Shutter Guide: Extruded Aluminium G70**
- **Operated by: Motor with one unit push button switch & manual override**

Sr .No.	Specification	Fire Rated Rolling Shutter - SKB BS 476
1	**Shutter Curtain**	SKB-F7D Double Walled Roll Form Steel with Rockwool Infilled
2	**Guide Rail**	Powder coated
3	**Bottom Bar**	Powder coated
4	**Type of Mounting**	Standard
5	**Motor Drive Unit**	Power Source: 230v 50Hz 1 phase Insulation Class E Manual Chain Override One unit push button switch Gravity drop level Auto close by relay switch after receive of 24vdc fire signal
6	**Standard RAL colors:**	RAL 9002
7	**Protection Category**	BS 476

2 Hrs Fire rated Door

Sr. No	Description	2 Hrs Fire rated Door
1	Description	Fire Resistant Door Single Leaf Hinge Type (2 Hour Fire Rated) 1.20 mm thick G.I Sheet cladded 46mm thick shutter with infill Material Mineral Wool (Density – 96 Kg/M3) complete with G.I. frame (Single Ribet – Frame Profile 100 x 57mm) made from 1.60mm thick G.I. Sheet & Fixing arrangements AS PER BS 476 (PART- 20 &22); IS: 3614 (Part-II) for Integrity, Stability. Paint Finish.
2	Door Size	1200mm (W) x 2100mm (H)
3	Accessories	S.S. Ball Bearing Hinges - 04 nos
		Panic Bar Exit Device for Single Leaf Door - 01 Nos
		External Trim bar Panic Latch - 01 Nos
		Vision Panel with Fire Rated Glass of Size: 200 x 300mm (6mm Thick Clear Toughened Glass)
		Heavy Duty Door Closer – Dorma Make TS 68
		Concealed Flush Tower Bolt - 01 Nos
		Door Stopper - 02 Nos

Single Leaf Steel Door without Panic Bar

Sr. No	Description	Steel Door
1	Description	General Purpose Steel (HMPS) Doors Single Leaf Hinge Type 0.80mm thick M.S. Sheet cladded 40mm thick shutter infill material as Honeycomb complete with M.S. frame (Single Rebate – 100 x 57mm) made from 1.20mm thick M.S. Sheet & Fixing arrangements. Finish – Paint Finish.
2	Accessories	S.S. Ball Bearing Hinges - 04 nos
		S.S. 'D' Type Handle - 01 Nos
		Dead Lock with Cylinder - 01 Nos
		Vision Panel with Non - Fire Rated Glass of Size: 200 x 300mm (6mm Thick Clear Toughened Glass) - 01 Nos
		Heavy Duty Door Closer – Dorma Make TS 68
		Door Stopper - 01 Nos

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 Weeks for Steel & Fire Door & 10-12 Weeks for 2 Hrs Rolling shutter from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Bhavin Jain on 8551092333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd