NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Godrej Construction
Godrej & Boyce Mfg. Co. Ltd.
Plant 25, Pirojshanagar,Vikhroli
Mumbai-400079, Maharashtra

Date : 14.02.2020
Quote NO : SQT.19.20.2397R1
Kind Attn : Mr. Yadvendrah Grigo
Email Id : ymgrigo@godrej.com
Contact No: 8238067626

Subject : Revised Quotation for Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	Option 1 : Grill 304L							
1	**Single Skin Motorised Rolling Shutter**	7500	6000	6	3,48,000	20,88,000	15,000	90,000
2	**Single Skin Motorised Rolling Shutter**	7500	8000	2	5,13,000	10,26,000	15,000	30,000
3	**Single Skin Motorised Rolling Shutter**	3000	3000	1	1,21,000	1,21,000	15,000	15,000
				Total		**32,35,000**		**1,35,000**
	Option 2 : Grill - MS							
1	**Single Skin Motorised Rolling Shutter**	7500	6000	6	3,02,000	18,12,000	15,000	90,000
2	**Single Skin Motorised Rolling Shutter**	7500	8000	2	4,67,000	9,34,000	15,000	30,000
3	**Single Skin Motorised Rolling Shutter**	3000	3000	1	1,02,000	1,02,000	15,000	15,000
				Total		**28,48,000**		**1,35,000**
4	P&F Charges on Total Supply Value			Nil				
5	Total without Taxes							
6	GST Extra @ 18%			18%		-		-
7	Total with Taxes					-		-
8	Transportation & Unloading Charges					**20,000**		
9	Scaffolding Charges					**40,000**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Make Single Skin Motorised Rolling Shutter

Sr. No	Description	Specifications
1	Rolling Shutter	Motorised Rolling Shutter with Galvalume steel of thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Curtain Panel	The panel made of 1.0mm thick Galvalume steel **Make : Jindal**
4	Curtain panel size	75mm wide
5	Curtain Profile	Curved
6	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with Bottom Rubber Seal
7	Side Guide Profile	1) M.S. wind Lock Guide profile 150 mm x 3 mm thick for Bigger Sizes 2) M.S. wind Lock Guide profile 100 mm x 3 mm thick for Small Sizes (3000 x 3000 mm)
8	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h **Make : Appolo Make**
9	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension
10	Hood Cover	Made of GI Sheet Thickness 0.9 mm **Make : Jindal**
11	Grill	**Pattern: Honeycomb** Option 1 : SS 304L - Make : **Jindal** Option 2 : MS - Make : **Jindal**
12	Surface finish	Powder coated **Make : Jotun Powder**
13	Motor	Indirect Drive **Make: Jielong - CE certified** **Motor Cable Length : 10 Mtr**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding Required for Installation at Site	Extra Prices as shown in above
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 40% Advance along with Confirmed Purchase Order, 50% Against Delivery & Balance after Installation.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of Installation.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards

Varsha
8551091333
For NIHVA Technologies Pvt Ltd