NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Karmaar SR Consultant
601-A/605, 6TH FLOOR, NEELYOG SQUARE, OPP. GHATKOPAR RWY STN,
R. B. MEHTA MARG, GHATKOPAR (EAST)., Mumbai- 400077

Date : 07.10.2020
Quote NO : SQT.20.21.2748
Kind Attn : Rajesh Ukey
Email Id : rajesh@karmaasrconsultants.com
Contact No: 9321167155

Project Name & Location:

Subject : Quotation for High Speed Fold up Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	High Speed Fold-up Door	3050	4390	1	350,000	350,000	20,000	20,000
2	High Speed Fold-up Door	7835	4390	1	780,000	780,000	20,000	20,000
3	High Speed Fold-up Door	7350	4390	1	750,000	750,000	20,000	20,000
			Total			**1,880,000**		**60,000**
4			P&F Charges	3%		**56,400**		
			Total Without Taxes			**1,936,400**		**60,000**
			GST Extra @ 18%	18%		348,552		10,800
			Total With Taxes			**2,284,952**		**70,800**
5			Transportation Charges			**In Client Scope**		
6			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA High Speed Fold up Door

Product	High Speed Door-Fold up type (All Imported Components)
Door Dimension	2500 mm to 10000 mm useful
Width Min. /Max.	2500 mm to 8000 mm useful
Height Min. /Max.	Larger Dimension on request
Opening Direction	Vertical
Mounting Location	Inside of the bay, inside the building
Opening/Closing Speed	0.5m/Sec. -1.0m/Sec.
Curtain Material	Curtain is in PVC made by anti-tear polyester fabric
Curtain Weight	680 gr/sqm
Tensile Strength	DIN 53354 - DIN EN ISO 1421/met. 1 – 2500/2500 N/50 mm
Stiffeners	Polycorbinate pipes
Tear Strength	Warp/Weft DIN 53363 – 250/250 N
Temperature range	-30°C +70°C
Flame Resistance	reaction in class 1 or 2
Vision Panel	One row of transparent PVC windows, in rectangular size, assures a good
Fabric Color	Standard Blue, Grey, Red
	Optional with various colors
Fold Up Arrangement	Segmented PVC curtain is folded up through lifting belt & tube mechanism
Roller Shaft	Tubular pipes with lifting belts
Side Guide Rails	Self supporting Galvanized steel structure
Bottom Profile	PVC profile
Side Brackets	Galvanized steel brackets with bearings
Hood Cover *(Optional)*	Galvanized steel
Control Type	Deadman /Pulse Control
Drive Unit	Electric Motor / Single Phase/Three Phase
Emergency Operation	Hand crank at top with drive
	Optional *chain mechanism*
Operating Switch	Push Button from Inside
	Optional-Push Button/Key Switch from Outside
Accessories (*Optional*)	Flashing Light
	Safety Photocell
	Remote Control with receiver
	Microwave Radar
	Pull Cord Switch
	Electronic Safety edge

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10-12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% along with confirmed purchase order & Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333.**

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd