**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Minda StoneRidge Ltd.**
Gut No. 287, 291, 295, 298, Nanekarwadi,
Chakan, Tal. Khed, Pune - 410501

**Date :** 09.12.2020
**Quote NO :** SQT.20.21.2873R
**Kind Attn :** Sandip Sakunde
**Email Id :** sandip.sakunde@mindastoneridge.com
**Contact No:** 9850897260

**Project Name & Location: Chakan, Pune**

**Subject : Quotation for Scissor Lift .**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|
| | | Working Platform (in mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **PORTABLE ELECTRO-HYDRAULIC SCISSOR LIFT 1 TON** | 1200 L X 1200 W | 1 | 234,000 | 234,000 | 15,000 | 15,000 |
| | | | **Total** | | **234,000** | | **15,000** |
| 2 | P&F Charges on Total Supply Value | | 3% | | 7,020 | | |
| | **Total Without Taxes** | | | | **241,020** | | **15,000** |
| | GST Extra @ 18% | | 18% | | 43,384 | | 2,700 |
| | **Total With Taxes** | | | | **284,404** | | **17,700** |
| 3 | Transportation Charges | | | | **In Client Scope** | | |
| 4 | Unloading Charges @ Site | | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification -**

**Electro Hydraulic Mobile Scissor Lift**

| Sr. No | Description | Specifications |
|---|---|---|
| 1 | **Capacity** | 1000 |
| 2 | **Platform size** | 1200 mm( L ) X 1200 (W) mm |
| 3 | **Shut ht** | 1000 mm |
| 4 | **Max ht** | 3500 mm |
| 5 | **Lift ht** | 2500 mm |
| 6 | **Power pack ( RAL 1004 )** | 3 HP, 3 Phase, 3.4 LPM |
| 7 | **Control Panel** | 3 HP STD |
| 8 | **Color** | GOLDEN YELLOW |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Amol Gaware on 7758820333.**

**With Best Regards**
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd